


Competitive State-of-the-Art Structural Engineering

Design and Manufacturing of Steel Bridges in the Alaskan Arctic



A Thesis Presented to the University of Alaska, Fairbanks (UAF)

Honors Program as Partial Fulfillment toward

Graduation and the Completion of the

Honors Thesis Scholar

By

Daniel P. Hjortstorp

04/20/2015

Dr. Leroy Hulseby P.E., S.E., _____

Professor: UAF Civil Engineering Department

Date _____

Dr. Marsha Sousa _____

Director: UAF Honors Program

Date _____

i. Table of Contents

Section

- i. Table of Contents
- ii. List of Figures and Tables
- iii. Acknowledgments
- 1. Abstract
- 2. Introduction
 - I. What is the Steel Bridge Competition?
 - II. Why Participate in the Steel Bridge Competition?
 - III. My Experience with the UAF Steel Bridge Team
- 3. Methods
 - I. Recruiting Interest, Fundraising, Charity, and Community Involvement
 - II. CAD Design and Analysis
 - III. Bridge Manufacturing and Machining
 - IV. Competition
- 4. Results and Discussion
 - I. Competition Results
 - II. Lessons Learned
 - III. Networking/Resume Building
- 5. Conclusion
- 6. Appendices
 - I. Appendix A
 - i. References
 - II. Appendix B
 - i. Pictures
 - ii. Figures
 - iii. CAD Drawings
 - iv. Fundraising Material
 - III. Appendix C
 - i. CNC Shop Drawings and 2015 Steel Bridge Rules



ii. List of Figures and Tables

I. *List of Figures*

<i>Figure Number</i>	<i>Page</i>
Figure 1: Assembly of the 2013 bridge...	10
Figure 2: 2013 UAF Steel Bridge team with awards...	10
Figure 3: The 2014 UAF Steel Bridge at regional competition...	11
Figure 4: The 2015 UAF Steel Bridge timed-assembly practice...	12
Figure 5: The 2015 UAF Steel Bridge build team	13
Figure 6: The 2015 UAF Steel Bridge Team	13
Figure 7: Construction site plan (at the competition)	17
Figure 8: Early prototype of an undertruss bridge...	18
Figure 9: Overtruss analyzed in RISA	18
Figure 10: RISA 3-D analysis of an overtruss bridge	19
Figure 11: RISA has many settings for changing the material...	19
Figure 12: Tension test of a prototype T-slot connection...	20
Figure 13: Prototype T-slot and <i>Autodesk</i> Simulation results	20
Figure 14: Final Bridge design overview	21
Figure 15: Stringer shop drawings	21
Figure 16: Prototype T-slot shop drawings	22
Figure 17: Machining and manufacturing	24
Figure 18: Regional Champions!!!	25
Figure 19: Welding	32
Figure 20: Bridge assembly practice	33
Figure 21: Setting up each piece before the timed assembly...	33
Figure 22: Applying the 2500 pound load...	34
Figure 23: Connections	34
Figure 24: Jig for cutting 4130 round tube in the mill...	35
Figure 25: networking through the AGC Student Club	35
Figure 26: Recruiting interest among students	35
Figure 27: Community service...	37



Figure 28: AGC News Letter...	38
Figure 29: Leadership certificate	39
Figure 30: Axial forces traveling through members...	40
Figure 31: CAD drawing of male-female connections	40
Figure 32: Analyzing sleeve connections with <i>Autodesk Simulation</i>	41
Figure 33: Analyzing sleeve connections with <i>Autodesk Simulation</i>	41
Figure 34: Fundraising Postcard	43
Figure 34: Fundraising Postcard	43
Figure 34: Fundraising Update	44

II. List of Tables

<i>Table Number</i>	<i>Page</i>
Table 1: The six load cases along with deflection targets	16



iii. Acknowledgments

I would like to thank Dr. Leroy Hulsey and Wilhelm Muench for their assistance and guidance in this project. Without their input, insight, inspiration, and help, this academic learning experience would have never been possible.

I would especially like to thank Eric Johansen, Joe Michalski and all team members who participated. The annual steel bridge competition requires huge time commitments from individuals who are already deprived of time due to stringent academic agendas.

Most importantly, I would like to thank my fiancée, Emily McCarthy, for putting up with me during the 2013, 2014, and 2015 steel bridge years. Participation in the Steel Bridge project requires large time commitments causing large strain on relationships and personal commitments.

Finally, I would like to thank the 2015 Steel Bridge supporters (we could not have done it without you):

ACI Alaska Chapter, Inc.

Alyeska Pipeline Service Company

American Institute of Steel Construction, Inc.

American Society of Civil Engineers (ASCE)

Associated General Contractors of Alaska (AGC)

Chevron Humankind Employee Engagement Fund

CRW Engineering Group

Design Alaska, Inc.

Fairbanks Elks Lodge No. 1551

Hector's Welding, Inc.

Institute of Northern Engineering (INE)

JCL Engineering, LLC

PM & E Services, LLC

Robert S Pamela E Hansen Living Trust

Kiewit Building Group Inc.

CESTiCC

Sherman Engineering, LLC

Carlile Shipping

Great Northwest Inc.

Utility Services of Alaska, Inc.

Petrotechnical Resources Alaska

Zarling Aero and Engineering

Mr. and Mrs. Roger A. Dombrowsk

Mr. and Mrs. Michael D. Hall

Ret. Col. Wayne A. Hanson

Mr. and Ms. Jacob E. Horazdovsky

Mr. and Mrs. Larry Isgrigg

Mr. and Mrs. Bryan H. Johnson

Mr. and Mrs. Clark Milne P.E.

Mr. and Mrs. Harold R. Moesser

Mr. and Mrs. Arthur W. Morris

Mr. and Mrs. Kenneth A. Risse

Dr. Yuri Shur and Ms. Tamara Zhestkova

Ms. Cynthia A. Stragier

Jim Moody

James Collier

Martin Gray

Richard Ward

Dr. Robert Perkins

And many more...



Abstract

The annual Steel Bridge competition was created over two decades ago to foster excellence and ingenuity among civil engineering undergraduate and graduate students across the nation. The steel bridge competition is one of many great opportunities to get involved in extracurricular activities associated with the civil engineering field. The University of Alaska Fairbanks (UAF) has a long history of strong performance. We are nationally known for placing well in both the regional and national competition. Students design and manufacture 1/10 scale bridges with which they compete in a regional competition and if successful a national competition. The Pacific Northwest (PNW) Regional conference is usually held mid-April each year. Much preparation and work led up to this high point of the year. The steel bridge competition teaches students valuable skills that few other engineers have the chance or ability to learn, making steel bridge team members extremely valuable employees to their future employers. Together, students tackle and overcome tremendously technical work under conditions such as extreme sleep deprivation and strenuous class loads. As a team we overcame severe financial trials, technical challenges, and tight deadlines. The 2015 competition was held at the Idaho State University in Pocatello, Idaho. The UAF Steel Bridge team swept the competition by winning seven out of seven categories and will compete for the national title on May 23rd in Kansas City. In addition to designing and building a steel bridge, members of the team also fulfilled hundreds of hours of community service and public speaking. They also support and comprise the core of the UAF Associated General Contractors (AGC) and the American Society of Civil Engineers (ASCE) student organizations. Steel bridge members sacrifice time with loved and dear ones as well as sleep and time allotted for homework in order to conquer one common goal; to design and manufacture the best bridge in the Pacific Northwest!!!



2. Introduction


1. What is the Steel Bridge Competition?

The annual Steel Bridge competition is organized by the (ASCE) to foster excellence and ingenuity among civil engineering undergraduate and graduate students across the nation. Student membership to ASCE is free for students and it comes with many benefits. ASCE has tremendous opportunities for networking and professional development as well as access to a wide variety of cutting-edge publications and journals. The steel bridge competition is one of many great opportunities to get involved in extracurricular activities associated with the civil engineering field.

The regional steel bridge competitions are held at the ASCE regional student conferences in conjunction with a concrete canoe competition, an environmental challenge, a transportation challenge, and a technical paper competition. Most of these competitions are standalone but UAF generally participates in all five competitions with great success. The top schools from each regional conference get invited to the national steel bridge competition, held at University of Missouri – Kansas City this year. As mentioned before, each competition is standalone; submission of the technical paper is, however, required as part of qualifying for the national steel bridge competition.

UAF has a long history of strong performance. We are nationally known for placing well in both the regional and national competition. UAF were national champions in 1993 and seldom place lower than top 20 in the nation out of over 200 competing schools. Many of these universities are prestigious engineering schools such as University of California - Berkley, University of California - Davis and Michigan Institute of Technology (M.I.T.). These Universities have large budgets and outside contractors to do some or all of the manufacturing. UAF students proudly complete the entire process, from fundraising to design and fabrication in-house.

The rules and specifications for the competition are generally made official (distributed) early September. The entire design and manufacturing process is focused on these specifications (the official rules). Similar to real world projects, regulations and industry standards govern the final product greatly. The rules can best be described as a bid document for a real world river crossing where the site conditions and the desired bridge performance specifications are clearly outlined. The bridges are designed and manufactured to 1/10 scale according to the specified requirements of overall span (in order to cross the river), the required vehicle passage way and the required lane width (to make sure that vehicles and semi-trucks will be able to pass across the bridge), the largest possible member size (in



order to be able to transport the pieces to the site based on local road restrictions and equipment assembling the bridge), and the approved types of connections. Large emphasis is put on accelerated bridge construction (ABC) in order to save money and time during manufacturing and assembly of the bridges on site.

There are three main factors affecting the final score of the 1/10 scale bridges in the competition. These factors are: weight of the bridge (pounds), stiffness of the bridge (aggregate deflection measured in inches at three locations and summed to create the aggregate deflection used for scoring), and time to assemble the bridge (minutes). These factors are entered into a formula that converts the three factors (weight, stiffness, and time to assemble) into a dollar amount. The bridge with the lowest calculated dollar cost wins the competition. The factors used to determine the score simulate that of a real-world low-bid process. The weight represents the material cost (structural steel is priced per pound of material), the time required to assemble the 1/10 scaled bridge at the competition simulate the amount of man-hours (labor cost) that's required to erect a full-scale bridge, and the stiffness of the 1/10 scale ensures proper serviceability of the full-size bridge. Engineers need to design structures not only to be sufficiently strong, but also to serve clients' needs. Humans generally feel uneasy if large deflection is sensed (regardless of the actual strength of the structure). An example of this may be the attic of an old wooden house where the floor joists may creek and deflect causing unease despite being adequately strong to support the load. Serviceability (deflection) is therefore an important factor to consider in design; hence the steel bridge rules force engineering students to meet certain deflection targets with their bridge designs.



II. Why Participate in the Steel Bridge Competition?

The steel bridge competition challenges and inspires students. It is easy to design a bridge, but extremely tedious and challenging to design a highly competitive bridge for the national arena. The steel bridge project also prepares students for the world outside of academia. Traditional academic education is extremely valuable and important in today's competitive work environment. Engineering degrees help students develop a problem-solving approach that may be applied to almost any challenge. Traditional degrees, however, fail to give students real world experience and skills necessary to prepare graduates for successful professional development. The steel bridge competition helps students gain a lot of valuable skills that traditional academic education fails to offer such as, machining, welding, design, fundraising, community involvement, and public speaking as well as project management and team work. Steel bridge is an excellent opportunity for students to gain experience by seeing an entire project come together from start to finish. It is especially valuable to manufacture what you design. Participants in steel bridge develop a keen mind for innovative problem solving and unmatched work ethic. It requires late nights, early mornings, all-nighters, and everything in between to complete the design and manufacturing of a competitive bridge. It is not uncommon for students to spend over 100 hours of their spring break, and 40-60 hours a week working on the bridge throughout the spring semester. We commonly run manufacturing close to 24/7 during the last weeks before the competition. Students will volunteer to come to the shop at 2 a.m. to pull a night shift or stay all afternoon until class starts in the morning at 8 a.m. Last but not least, the steel bridge competition opens a lot of doors for future employment through the networking and community involvement that is required to fund-raise for the program each year. Employers recognize this drive and motivation to excel, often seeking out steel bridge participants for future hiring.



III. My Experience with the UAF Steel Bridge Team

I got engaged with Steel Bridge in 2013 after becoming friends with some of the key bridge members through the UAF Ice Arch construction. The 2013 UAF steel bridge (designed by Pat Brandon) dominated at the regional competition by winning the following categories (*the categories in parentheses are separate side competitions*):

REGIONALS

1st place Structural Efficiency
1st place Stiffness
2nd place Lightness
2nd place Construction Economy
(1st place Environmental Engineering Competition)
(2nd place Transportation Engineering Competition)
(Overall Engineering Excellence Award)

NATIONALS

3rd place Structural Efficiency
3rd place Deflection
(1st place Tug-of-War)



Figure 1: Assembly of the 2013 bridge at the National Competition.



Figure 2: 2013 UAF Steel Bridge team posing with awards for 3rd stiffest and 3rd in structural efficiency at Nationals at University of Washington.



The 2014 steel bridge (designed by Will Riley) was a structural master piece requiring tremendous amount of work to manufacture and weld. There were over 700 individual pieces milled and machined to a precision of 1/1000 of an inch and at least 1500 welds to complete. Due to the tremendous amount of work, both dayshifts and nightshifts were scheduled in the machine shop in order to keep the machinery on the critical path working 24/7. This time commitment was tremendous for students who already spent over 80 hours a week going to class and finishing school assignments. The 2014 bridge would most likely have won both the regional and national competition had there not been a local buckling failure causing welds to break.



Figure 3: The 2014 UAF Steel Bridge at the regional competition at the Portland State University.

The 2015 rules were very similar to the rules in 2014. The dimensional specifications and the loading were almost identical. The major changes in the rules were the overall span (18.5 feet instead of 17 feet) and more freedom to design innovative and quick-to-assemble connections. The 2015 bridge (designed by Daniel Hjortstorp) sported a delicate lower chord spanning 19.5 feet along with a stout $1\frac{3}{4}$ inch upper chord. The bridge had a clearance of 19 inches over the river and a total height of 59 inches. Just as previous years, the bridge was manufactured out of 4130 chrome molly steel and assembled with aircraft quality nuts and bolts. Much attention and time was spent designing and manufacturing state of the art connections for the bridge to allow for quick assembly. Members in the space truss were



standardized to accelerate the manufacturing process.



Figure 4: The 2015 UAF Steel Bridge timed-assembly practice (regional competition in Pocatello, Idaho).



Figure 5: The 2015 UAF Steel Bridge Build team (after the timed assembly).



The steel bridge project has been a tremendous fountain of knowledge creating unmatched experience, skills, and friendship. In 2013 I learned to use the equipment in the machine shop and competed with the bridge as a one of four UAF builders at both the regional and national competition. In 2014, I was assigned as the student in charge of the steel bridge manufacturing, and in 2015 I designed the bridge and led the team as the team captain. It has been an unforgettable journey full of a lot of hard work and unforgettable memories and laughs that have contributed more to my academic development than both coursework and traditional academic learning. I am forever thankful for the opportunity to participate in the UAF steel bridge program and look forward to become a strong alumni supporter.




Figure 6: The 2015 UAF Steel Bridge team.



3. Methods

1. Recruiting Interest, Fundraising, Charity, and Community Involvement

Recruiting is one of the most important activities to maintain a competitive team. As a team captain, developing interest in the steel bridge project among fellow students and classmates is a constant task. Our team furthermore spends countless hours advertising and promoting the steel bridge team at our weekly joint meetings with the ASCE and the AGC student organizations. We also take every opportunity to meet and get to know freshman and sophomores. We arrange barbeques and talk to freshmen classes such as ES101 and surveying for engineers. We also spend much time building relationships with local businesses, trade organizations, and professional organizations such as Chamber of Commerce, Rotary, the Society of Structural Engineering and American Concrete Institute through community service and public speaking. We collected close to 1200 pounds of canned food for the canned food drive last weekend and built bunk beds for homeless people in North Pole just to mention some of the community service. All together, we (the students that are part of the steel bridge team) have fundraised \$50,000 for the 2015 steel bridge to cover the expenses of materials, travel, equipment, and machinery to maintain the shop (see Appendix B for more information regarding the fundraising efforts).



II. CAD Design and Analysis

The 2015 Steel Bridge rules were made available in September after which the design process was started. The design process is extremely tedious due to the competitive component to the project. It is easy to design a bridge that will be adequately strong, but it requires an exhausting amount of iterations to develop a competitive design. The first step of any design is to carefully examine and read the bid packet and specifications (in this case the 35 page long packet of competition rules). The design of the bridge is, in large part, governed by the dimensional specifications and calculated score scale outlined in the rules. The rules change each year, making it extremely important to carefully examine the most current rules for areas that may have changed. The rules commonly outline a mission and summary:

“Civil Engineering students are challenged to an intercollegiate competition that supplements their education with a comprehensive, student-driven project experience from conception and design through fabrication, erection, and testing, culminating in a steel structure that meets client specifications and optimizes performance and economy. The Student Steel Bridge Competition increases awareness of real-world engineering issues such as spatial constraints, material properties, strength, serviceability, fabrication and erection processes, safety, aesthetics, project management, and cost. Success in competition requires application of engineering principles and theory, and effective teamwork. Future engineers are stimulated to innovate, practice professionalism, and use structural steel efficiently” ... The Student Steel Bridge Competition provides design and management experience, opportunity to learn fabrication processes, and the excitement of networking with and competing against teams from other colleges and universities (2015 National Steel Bridge Student Competition, 2015).

The 2015 (simulated) problem statement was set forth by President Kupicra who requested a bridge over the Nogo River to encourage commerce between farming villages and the capital, H’sogo. Bridge materials had to be transported on ox carts during the dry season making accelerated bridge construction (ABC) essential to achieve completion before the rainy season. There are several categories in the competition: aesthetics, construction speed (timed assembly at the competition), lightness, stiffness, construction economy, structural efficiency, and most importantly – *Overall Performance* (determining the winner of the competition). Most of these categories are quite self-explanatory.



The construction speed is the time it takes to assemble the bridge at the competition with time penalties added. Each connection violation adds three minutes to the overall score, hence this may ruin the low score of a bridge significantly. Lightness is awarded to the lightest bridge after weight penalties have been added. Dimensional violations may add 50 to 200 pounds to the original weight of the bridge. Similarly, stiffness is a simple measure. There are six different load cases (determined by the roll of a dice before the competitions begin) at which 3 deflections are taken and added up to an aggregate deflection.

Table 1: The six load cases along with deflection targets.

(S=Loadcase, T=Deflection Target, L=Load)

S	T1	T2	L1 (lb)	L2 (lb)
1	9'9"	12'3"	1000	1400
2	7'9"	9'9"	1400	1000
3	7'9"	12'3"	1200	1200
4	7'3"	10'9"	1200	1200
5	7'3"	11'9"	1000	1400
6	9'3"	11'9"	1400	1000

The construction economy is calculated from the construction speed by taking the time to build the bridge times the number of builders that build the bridge. The maximum number of builders is six and the maximum construction speed (straight time) allowed is 30 minutes. The construction economy is calculated as follows: *Construction Economy = Total Time (minutes) x number of builders (persons) x 50,000 (\$ per person-minute) + load test penalties (\$)*

Hence a bridge built in 20 minutes by 4 builders would score \$4,000,000 in the Construction Economy category provided there were no penalties. One of the larger penalties this year was associated with the river at the simulated construction site at the competition.






Figure 7: Construction site plan (at the competition).

Structural Efficiency is the second major category that determines the overall score of the bridge. The Structural Efficiency is calculated with the following formula (for bridges weighing less than 400 pounds): *Structural Efficiency = Total Weight of the Bridge (pounds) x \$20,000 (\$/pound) + Aggregate Deflection (inches) x \$1,000,000 (\$/inch) + load test penalties (\$)*

There is a separate formula for bridges weighing more than 400 pounds. However, bridges that heavy are not competitive at the national arena, thus the formula will not be covered in detail. The *Overall Performance* is calculated by adding the construction economy and the structural efficiency (determining the winner of the competition).

The design of each bridge should be based on the details above in order to be competitive; hence, a bridge that is highly competitive one year may not be competitive in the following years due to rule changes thus designers are encouraged to develop new innovative and competitive designs each year based on countless simulations in structural analysis programs and material research. The design process is extremely tedious and strenuous as mentioned previously. The first stage is comprised of careful examination of the rules. Each detail and change is carefully analyzed to find areas that may allow for improvements and advantages over other schools. Inadequate familiarization with the rules is one of the most common mistakes that many schools make. Special care has to be taken to ensure that assumptions are not made based on mixing up the rules of previous years with the current one. Once the rules have been carefully analyzed, a tedious process is started in which every single bridge shape imagined is drawn as a stick figure and analyzed in structural analyses programs. We currently use RISA, version 12, to analyze our designs. RISA is an extremely powerful structural analysis program. Below are some of the initial designs that were analyzed in the initial design phase.




Figure 8: Early prototype of an undertruss bridge analysed in RISA.




Figure 9: Overtruss analyzed in RISA.

RISA will show the deflection and stress of each member and joint, along with the overall weight of the structure making it extremely powerful for analysis. Once the final shape of the bridge has been determined - based on the 2-D analysis - the bridge is drawn in 3-D in AutoCAD and imported into RISA 3-D for further analysis and optimization.






Figure 10: RISA 3-D analysis of an overtruss bridge.




Figure 11: RISA has many settings for changing the material properties and careful analysis of the stress and deflection of members. The picture above shows the tension and shear in the bridge based on a 2500 pounds distributed across 6 feet at the center of the bridge.

Design and manufacturing requires a lot of effort. As James Dyson once said, “manufacturing is more than just putting parts together. It’s coming up with ideas, testing principles and perfecting the engineering, as well as the final assembly” (Wolfgang Arrasmith, 2015).



Altogether, over 400 files of different designs and modifications to the 2015 steel bridge were created throughout the design period between September and February. Once the overall shape of the bridge has been determined and the material and sizes assigned to each member (members can only be 36 inches long), much time was spent designing quick-to-assemble connections with sufficient strength. The connections were drafted in *AutoCAD* after which they were analyzed with the help of *Autodesk Inventor* and *Autodesk Simulator*. *Autodesk Simulator* is a finite element analysis program that analyzes stress and displacement by breaking elements into very small increments. These programs are extremely accurate but the output is only as good as the input; hence, it is important to verify the results with real data. We tested a T-slot prototype and many other connections in a straight tension test. The graph for the results can be seen in figure 12 below.




Figure 12: Tension test of a prototype T-slot connection pictured above.




Figure 13: Prototype T-slot and Autodesk Simulation Results (the deflections are exaggerated in the visual output results).



Once the final bridge design was created, the concept was turned into a workable format. The entire bridge consisting of over 300 individual members were broken down into separate pieces and shop drawings were created. The shop drawings have to convey enough information to machine each individual piece. The figure below illustrates a basic overview of the bridge before breaking it into smaller pieces.




Figure 14: Final Bridge design overview.



Figure 15: Stringer shop drawings.

Connections require far more drafting and machining to complete. Below is the shop drawing for the prototype T-slot pictured next. Appendix C includes the entire set of shop drawings for the interrupted thread quick connect threads that were programmed and machined with CNC technology.






Figure 16: Prototype T-slot shop drawings.



III. Bridge Manufacturing and Machining

The machining and manufacturing of the bridge is an extremely tedious and time consuming venture that requires thousands of hours of shop training and highly specialized labor. Machining helps engineers develop a keen sense for developing advanced design practices that enhance constructability and technical communication between design engineers and contractors in the real world. Over a dozen student team-members helped with the cleaning of the steel, rough cutting, milling, lathe work, and welding of the bridge. Altogether, over one thousand man hours went into the manufacturing of the final bridge. All students participating in the steel bridge manufacturing had to complete Job Hazard Analysis (JHA) forms as well as specific training for each individual piece of equipment (lathe, mill, welder, plasma cutter, drill-press etc.) The steel for the bridge was ordered from Stock Car Steel and Aluminum in North Carolina. Stock Car Steel provides extremely reliable shipping and handling and carries some of the rarest sizes of 4130 steel, steel found only with extremely specialized Nascar suppliers. The 4130 steel that we use for the bridge has excellent strength and unmatched precision compared to regular mild steel. Each piece of the bridge has to be milled to the precise length and angle (with a 1/1000" precision) requiring excellent skill and craftsmanship. The steel has to be cleaned of oil and mill scales once it arrives, after which it has to be rough cut and milled to the correct length and angle. Connections take even more time. It is not uncommon for a connection to have over a dozen different steps of manufacturing.







Figure 17: Machining and manufacturing.

IV. Competition

The Pacific Northwest (PNW) Regional conference is usually held mid-April each year. The 2015 competition was held at the Idaho State University in Pocatello, Idaho. Stiffness and weight of the bridge is in large dealt with through the design and manufacturing process. Since the assembly time is a large part of the total score, we commonly spend several days before the competition practicing the assembly of the bridge. Connections have to be polished and filed to fit perfectly, and the order of assembly is improved through carefully analyzed optimization of the assembly.

The competition is commonly organized as follows:

- Registration
- Practice assembly
- Display setup (judges score bridges based on aesthetics)
- Captains meeting (details are clarified before the competition get started)
- Timed assembly
- Dimensional penalty check
- Later loading (a 50 pound horizontal force is applied at the center of the bridge. Bridges deflecting more than an inch are disqualified)
- Vertical loading (2500 pounds is applied to the bridge after which deflection is measured)



4. Results and Discussion

1. Competition Results

The 2015 PNW Regional Steel Bridge Competition attracted thirteen schools to compete for the prestigious regional steel bridge first place (awarded to the bridge with the lowest overall calculated dollar score). Idaho State University took the third place with a calculated score of \$44,080,000; Oregon State University took second place with a total score of \$9,137,500; and UAF won the first prize with a large margin with a total score of \$5,465,000. Not only did UAF win the overall competition, we won every single one of the six side categories. Thus we had the lightest, stiffest, fastest, most aesthetically pleasing bridge, with the best construction economy and structural efficiency. UAF has competed really well in the past, but has never won all seven categories at the regional competition; thus, the 2015 regional competition is likely to be remembered for a long time. It is extremely hard to be the lightest bridge and still be the stiffest (strongest) bridge, since there is a close to inverse linear relationship between stiffness and weight of steel structures (for example, as the weight doubles the deflection is cut in half).




Figure 18: Regional Champions!!!



II. Lessons Learned


The lessons learned are many. It is evident that hard work gives good luck, but even more importantly, team work and a clearly defined common goal can overcome most all obstacles. Together we tackled and overcame tremendously technical work under conditions such as extreme sleep deprivation and strenuous class loads. We survived severe financial struggles, technical challenges, and tight deadlines. As a group we did so much more than simply designing and building a competitive steel bridge. We have completed hundreds of hours of community service and public speaking. We have supported and in many ways been the core of our AGC and ASCE student organizations. We have sacrificed time with loved and dear ones and given up personal time for a common goal; to design and manufacture the best bridge in the Pacific North West! We succeeded to conquer a common goal, but actually achieved more than we set sail to achieve. In the process, we gained important team-work skills, a work-ethic far above and beyond what's required by the common employer, and a personal drive for success that will benefit us no matter what industry or field of work we set out to conquer, and last but not least – unmatched friendship. Success does, however, require a lot of sacrifices. More than once, the goal and focus faded temporarily; but there was always someone in the group to provide encouragement and renewed focus. In summary, some of the most important lessons learned are:

- Each task will take at least three times longer than expected.
- Planning, planning, and more planning is required to keep a project on track and successful.
- Build a team and the product will build itself.
- Have fun and maintain good morale even when things are tough.
- Never let tasks on the critical path fall behind.
- Always have a backup plan.




III. Networking/Resume Building

It was the journey of the team, not the product that made it all worthwhile. Not only did we build a bridge that will be extremely competitive at the national competition against some of the largest Ivy League engineering schools, we built a team that, in my mind, could conquer anything it sets its aim on. The steel bridge competition creates unmatched camaraderie and unforgettable memories all while challenging and inspiring students, ultimately forming them into the productive and innovative engineers of the future. Maintaining a competitive Steel Bridge Team requires a total annual budget of \$50,000 (materials and travel); thus, students also gain extremely valuable fundraising and budget skills. We spend countless hours interacting with businesses, professionals, and organizations around the community in order to raise the support necessary to ensure UAF's legacy of elite national performance and prosperity will continue for new and future UAF CEM students alike.



5. Conclusion


The UAF Steel Bridge program offer students a great opportunity to get involved into an extracurricular activity associated with the civil engineering field. Participation gives students a lot of useful skills and experience that will ultimately prepare them for a lifelong professional career as a civil engineer. UAF has a long history of strong performance at both the regional and national competitions; once again proven by the strong performance at the 2015 regional competition at the Idaho State University, in Pocatello, Idaho. The UAF Steel Bridge team swept the competition by winning seven out of seven categories (for the first time in UAF history). UAF had the lightest, stiffest, fastest, most aesthetically pleasing bridge with the best construction economy and structural efficiency. The success of the UAF steel bridge team should however not be measured by the trophies and titles won, but rather by the camaraderie and educational advantage that the members of the 2015 steel bridge team has acquired through unmatched teamwork and focus on a common goal.



The potential professional development and growth that lie ahead of each member of the elite UAF steel bridge brotherhood is endless. I am thrilled to see each one of these extraordinary engineers spread across the nation to make the United States and the world a better place through sound and innovative engineering. Meanwhile, I hope that the strength of the UAF Steel Bridge program will continue to grow through sustained alumni and community support so that future students can receive the same exceptional opportunities that we received. Team-work lay at the base of the UAF Steel Bridge program. It is the transfer of knowledge between steel bridge generations that make us who we are... may the curiosity for learning and advancement never stagnate.

/ Daniel Hjortstorp

*Graduating Senior, B.S. Civil Engineering, UAF
2015 Steel Bridge Designer and Team Captain*



Appendix A

References

2015 National Steel Bridge Student Competition. *UMKC NSSBC 2015*. Retrieved from
<https://www.aisc.org/content.aspx?id=780>

Wolfgang Arrasmith, W. (2015). *Systems Engineering and Analysis of Electro-Optical and Infrared Systems*. Retrieved from: https://books.google.com/books?id=Zo-9BwAAQBAJ&pg=PA653&lpg=PA653&dq=manufacturing+is+more+than+just+putting+parts+together.+It%E2%80%99s+coming+up+with+ideas,+testing+principles+and+perfecting+the+engineering,+as+well+as+the+final+assembly&source=bl&ots=Cxf_qLzDnS&sig=sXLYt619doZ6Md-wG9HC_EKNMvI&hl=en&sa=X&ei=ewQ3Vdi1J5KhyASJ94GQDQ&ved=0CEUQ6AEwBw#v=onepage&q=manufacturing%20is%20more%20than%20just%20putting%20parts%20together.%20It%E2%80%99s%20coming%20up%20with%20ideas%2C%20testing%20principles%20and%20perfecting%20the%20engineering%2C%20as%20well%20as%20the%20final%20assembly&f=false

Sources of Information Accessed During the Design Process

ASCE/AISC Student Steel Bridge Competition Guide. (2015). *2015 Competition Guide*. Retrieved from:
<http://www.nssbc.info/History.htm>

Bridge Design and Engineering. (2015). *Bridge Design and Engineering*. Retrieved from:
<http://www.bridgeweb.com/Issue/Default.aspx>

Bridge Engineering. (2015). *Wabash Bridge Competition*. Retrieved from:
http://www.phlf.org/downloads/education/Edu_WabashBridgeDesign.pdf


Flemming, D. J. (2015). *Bridge Engineering: Committee on General Structures*. Retrieved from:
<http://onlinepubs.trb.org/onlinepubs/millennium/00013.pdf>

Hibbeler, R.C. (2010). *Engineering Mechanics: Statistics & Mechanics, Twelfth Edition*. New Jersey: Pearson Prentice Hall.

Hibbeler, R.C. (2012). *Structural Analysis, Eight Edition*. New Jersey: Pearson Prentice Hall.

Ketchum, M. (2015). *Mark Ketchum's Bridge Engineering Page*. Retrieved from:
<http://www.ketchum.org/bridges.html>

Kurtz, D.L. (2014). *Contemporary Marketing, Sixteenth Edition*. Mason: Cengage Learning.



Okyle, C. (2014). *10 Awesome Tips for Being a Better Leader*. Retrieved from:

<http://www.entrepreneur.com/article/238747>

Peurifoy, R. L. (2002). *Estimating Construction Costs, Fifth Edition*. New York: McGraw Hill.


RISA. (2015). *RISA 3-D: The Most Popular Structural Engineering Software in the U.S.* Retrieved from:

https://risa.com/p_risa3d.html

Segui, W. T. (2013). *Steel Design, Fifth Edition*. Stamford: Cengage Learning.

Stock Car Steel and Aluminum, Inc. (2015). *Best Online Source for Metals and Plastics*. Retrieved from:

<http://www.stockcarsteel.com/>



Appendix B

I. Pictures



Figure 19: Welding





Figure 20: Bridge assembly practice.




Figure 21: Setting up each piece before the timed assembly at the competition.





Figure 22: Applying the 2500 pound load with a pallet jack.




Figure 23: Connections.






Figure 24: Jig for cutting small 4130 round tube in the mill on the left. CNC'd interrupted threads on the right.



Figure 25: Networking through the AGC Student Club.



II. Figures




Figure 26: Recruiting interest among students.






Figure 27: Community service – **results of** a two day food drive effort.



Competitive State-of-the-Art Structural Engineering
University of Alaska, Fairbanks



Shaping tomorrow's leader's

The AGC Student Chapter Members were a large contributor to this year's winning team of the UAF Starvation Gulch.

After creating scaled construction, logistics, and safety plans, the giant pile of pallets took shape well within the small 4-hour window of time allowed. The "twin tower bridge" design concept required students to become resourceful, to work creatively within the rules, and to collect *thousands* of pallets after classes and homework.

Using some basic academic skills, hands-on ability, and competitive spirit, this group of students brought pride to the chapter, learned some valuable skills, and had some fun in the process. Also, the project attracted several Freshmen, and helped to recruit new members.



The bonfires have been a symbol of the passing of the torch of knowledge to new students at UAF since 1923.



Top: Student Chapter members pose after completing the construction of a bonfire for Starvation Gulch. It was the only bonfire with a scaled drawing, and construction plan.
Bottom: Bonfire lights up the night, with the letters "UAF CEM" back-lit by flames.

Helping Those in Need

Members from the UAF AGC Student Club had the opportunity to give back to the community by building bunk beds for a relocated homeless family. Students volunteered their Halloween Weekend to build and deliver these beds to a family of six kids in great need.



AGC members helping to build bunk beds.

Figure 28: AGC newsletter we created to gain student and community interest in what we do through AGC Student Club (reaching out to homeless among one).





Figure 29: Leadership certificate.



III. CAD Drawings




Figure 30: Axial forces traveling through members in the final bridge design.




Figure 31: CAD drawing of male-female connections.






Figure 32: Analyzing sleeve connections with *Autodesk Simulation*.





Figure 33: Analyzing sleeve connections with *Autodesk Simulation*.



IV. Fundraising Material

UAF ASCE Student Chapter



306 Tanana Drive, 245 Duckering Building; P.O. Box 755900, Fairbanks, Alaska 99775-5900 ~ (907) 474-7241 ~ Fax (907) 474-6807
fycee@uaf.edu ~ www.uaf.edu/engineering/cee.htm

November 10th, 2014

Dear Supporter,

We are asking for your support of our dedicated engineering teams here at the University of Alaska Fairbanks. The annual ASCE/AISC Steel Bridge and Concrete Canoe Competitions creates the opportunity for UAF's College of Engineering and Mines (CEM) to consistently display its educational successes through some of the nation's most talented engineering students. Where larger schools provide the budgets and outside contractors do an excessive amount of work, UAF students proudly complete the entire process, from fundraising to design and in-house fabrication.

The UAF Steel Bridge Team has a long history of strong performance. We are nationally known for placing well in both the regional and national competition. We hope to continue this tradition of excellence with your support.

The UAF Concrete Canoe Team put in hundreds of hours last year constructing and designing an innovative floating concrete canoe to enter the competition for the first time in UAF history. This year's challenge of building a newly-designed, lightweight and structurally sound canoe will provide a strong foundation for current and future student growth.

Today, we ask for an early 2015 contribution to support our efforts. These competitions challenge and inspire the students, ultimately forming them into the productive and innovative engineers of the future. Maintaining a competitive Steel Bridge and Concrete Canoe Team requires a total annual budget of \$60,000 (materials and travel). **With your support, we can ensure UAF's legacy of elite national performance and the prosperity of new and future UAF CEM students alike.** To learn more, please visit us on the web at cem.uaf.edu/news/2013-steel-bridge-regionals.

You may donate by mail (see envelope and card enclosed) or online at the following secure site: cem.uaf.edu/giving and follow the link to the **ASCE Student Competition Support Fund (Steel Bridge & Concrete Canoe)**. You will receive a receipt from the UA Foundation for your donation for tax purposes.

Thank you for your time, generosity and support of our growing program.

Sincerely,
The UAF Steel Bridge and Concrete Canoe Competition Program

Steel Bridge Project Manager

Concrete Canoe Project Manager

UAF is an Equal Opportunity Employer/ Affirmative Action Educational Institution






Figure 34: Fundraising Postcard.




Figure 35: Fundraising Postcard.





Figure 36: Fundraising Update.



March 23rd, 2015

Chancellor Brian Roger,

The Regional Steel Bridge and Concrete Canoe Competitions will take place during the ASCE Student Conference at the Idaho State University between April 16th and April 18th. We are asking for your help to support our dedicated engineering teams as they travel to the competitions where they will represent the University of Alaska (UAF) in the Steel Bridge Competition, Concrete Canoe Competition, Environmental Challenge, Transportation Challenge, and Technical Paper Competition.

Travel dates will be April 15th– April 19th. Flights to Pocatello, Idaho currently cost \$1,041.00 but are certain to increase as the travel dates quickly approach. We have already booked hotels in Pocatello at the Rodeway Inn between April 15th and April 19th for students and faculty traveling and have two minivans quoted at \$611 per vehicle. In addition, we will need to cover the expenses of transporting both the bridge and canoe to the competitions. The bridge may be shipped as luggage on the airplane and the canoe will be trucked to a logistical hub in the states. Rental of a U-Haul to transport the canoe from Seattle or Tacoma to Pocatello may cost up to \$2,000 once mileage charges have been added.

The UAF Steel Bridge Team has a long history of strong performance. We are nationally known for placing well in both the regional and national competition. The UAF Concrete Canoe Team dedicated hundreds of hours last year constructing and designing an innovative floating concrete canoe to enter the competition for the first time in UAF's history. This year's challenge of building a competitive lightweight and structurally sound canoe will provide a strong foundation for current and future student growth. These competitions challenge and inspire the students, ultimately forming them into the productive and innovative engineers of the future.

Due to Alaska's location, we have large travel expenses compared to other universities in the nation. Our students have spent countless hours fundraising and promoting our efforts to the community to raise the money to purchase materials and supplies for construction of these projects.

We are asking for your financial support covering the airfare for four ($\$1,041 * 4 = \$4,164$) of the students traveling to the Regional ASCE Student Conference where will display UAF's College of Engineering and Mines (CEM) educational practices through some of the nation's most talented engineering students at the Steel Bridge, Concrete Canoe, and many other academically challenging competitions.

Thank you for supporting our academic growth and learning.

Sincerely,
Daniel Hjordstorp
Steel Bridge Team Captain
dphjordstorp@alaska.edu
(907) 320 6078



UAF Steel Bridge Team


306 Tanana Drive, 245 Duckering Building; P.O. Box 755900, Fairbanks, Alaska 99775-5900 ~ (907) 474-7241 ~ Fax (907) 474-6807
fycee@uaf.edu ~ www.uaf.edu/engineering/cee.htm

February 6th, 2015

Dear Jim,

We are excited to yet again gather forces for another ASCE/AISC Steel Bridge Competition. The 2015 Steel Bridge rules are quite similar to last year's rules except for a few distinct changes. The scoring is almost identical but the overall span of this year's bridge has increased to 18.5 feet compared to last year when we only had to span 17 feet. Furthermore, certain penalties have increased dramatically making it crucial to avoid mistakes during the timed assembly at the competition.

This year's competition has attracted a lot of interest, especially among younger students, making the outlook for our 2015 UAF Steel Bridge Team bright. The team has met on a regular basis since the fall to collaborate on design and discuss building methods that conform to the new rules. The bridge features a slender space truss for the bottom chord combined with a stout upper chord that will help avoid unexpected behavior under compression.



2015 Steel Bridge Design

The bridge will be constructed out of 4130 round tube except for the decking surface and the legs that will be made out of box tube. We are currently developing shop drawings, checking the RISA computer analysis with hand calculations, and detailing connections while waiting on steel to arrive. The regulations for connections once again make it possible to apply engineering knowledge and ingenuity into the connection-design (unlike the last three years when the regulations for connections dampened creativity). We are currently designing and brainstorming different connections in order to carry on the long tradition of excellent connections that UAF is nationally known for. We currently expect to start machining pieces for the bridge later this week with some of the supply that we already have in stock.

We really appreciate your support and devotion to ensure a bright future for the UAF Steel Bridge program. The Steel Bridge Competition challenge and inspire students, ultimately forming them into productive and innovative engineers of the future. Your donations help us ensure that UAF's legacy of elite national performance endures and that the prosperity of new UAF CEM students will continue long into the future through the Steel Bridge Program.

Sincerely,

The 2015 Steel Bridge Team

UAF is an Equal Opportunity Employer/ Affirmative Action Educational Institution



Appendix C

I. CNC Shop Drawings and 2015 Steel Bridge Rules




Top Chord MALE Connection (SIDEVIEW)

Made out of 1.75" by 0.120" Round Tube

Qty: ~~2~~+ Extra

Date: 3/14/2015




Top Chord FEMALE Connection (SIDEVIEW)

Made out of 1.75" by 0.120" Round Tube

Qty: ~~4~~ + Extra

Date: 3/14/2015

1/4




Top Chord MALE Connection (SIDEVIEW)

Made out of 1.75" by 0.120" Round Tube

Qty: 14 + Extra

Date: 3/14/2015

3/24/2015




Top Chord FEMALE Connection (SIDEVIEW)

Made out of 1.75" by 0.120" Round Tube

Qty: 14 + Extra

Date: 3/14/2015

3/24/2015




Stringer MALE Connection (SIDEVIEW)

Made out of 1.75" by 0.120" Round Tube

Qty: 6 + Extra

3/14/2015

6




Stringer FEMALE Connection (SIDEVIEW)

Made out of 1.75" by 0.120" Round Tube

Qty: 6 + Extra

3/14/2015

6




THICK MALE Connection (SIDEVIEW)

Made out of 1.75" by 0.120" Round Tube

Qty: 4 + Extra

3/14/2015

✓




THICK FEMALE Connection (SIDEVIEW)

Made out of 1.75" by 0.120" Round Tube

Qty: 4 + Extra

3/14/2015



u



Quick Connect Female #1

Connecting to $\frac{1}{2}$ " by 0.049

Qty: 2



Daniel

3/20/2018


907 320 6078

~~5/11/18~~
~~5/11/18~~

Quick Connect Male #1

Connecting to $\frac{1}{2}$ " by 0.049


Qty: 2



Quick Connect Male #2

Connecting to $\frac{1}{2}$ " by 0.035



Qty: ~~46~~



Quick Connect Female #2

Connecting to 1/2" by 0.035


Qty: ~~4~~ 6



Quick Connect Male #3

Connecting to 1/4" by 0.035


Qty: 8







Quick Connect Female #3

Connecting to 1/4" by 0.035

Qty: 8






0.0157 in2

0.0086 in2 = 54.77%


Ø0.7500 — Ø0.5186



Ø0.1875


Ø0.2500


Ø0.1250




60°

$\frac{1}{2}$ " - 13 Threads per Inch - Swedish Steel Bridge Custom Unified Non-Standard Special Champion Thread





Pitch DIA .482



~~$\varnothing 0.4000$~~
.404

FEMALES

QTY: TBD

Operation #1


Drill Center Hole $\frac{1}{4}$ " Hole DRILL $2\frac{5}{64}$

X - 0.0000

Y - 0.0000

Z - .670

(Red = Active Operation)





Operation #2


Drill $\frac{1}{8}$ " Holes

Radius 0.2075 "


Angle




Operation #3
Mill 0.3668" hole by
turning a $\frac{1}{4}$ " mill a full revolution
at a turn radius of 0.0584" from
X - 0.000 and Y - 0.000



Operation #4
Mill out between
 $\frac{1}{8}$ " hole with $\frac{3}{16}$ " Dia. mill
Radius 0.1603"
Angle





Operation #4
Mill out between
 $\frac{1}{8}$ " hole with $\frac{3}{16}$ " Dia. mill
Radius 0.1603"
Angle



**Operation #5
Thread-Mill the Female**

Use MSC 1/2 -13 Carbide
Internal and External Thread-Mill
OAL - 3.5"
LOC - 1.0"
Number Flutes 4
Cutter Dia - 0.400"
Order # 60023504
\$213.15
Page 335 MSC 2006/2007 Catalog



MALES



QTY: TBD

Operation #1

Drill $\frac{1}{8}$ " Holes into $\frac{3}{4}$ " stock

Radius 0.2439"

Angle




Operation #2A

Neck down the $\frac{3}{4}$ " to $\frac{1}{2}$ " for the length of the connection

IF using a $\frac{1}{2}$ " End-mill the turn-radius is $\frac{1}{2}$ "

(Red = Active Operation)




Operation #2B
Neck down the bullet nose to
0.3668 or smaller
with method of choice.

I

Operation #3
Mill out between $\frac{1}{8}$ "
holes with $\frac{1}{4}$ " End-Mill



Radius 0.2914
Angle



**Operation #5
Thread-Mill the Female**

**Use MSC 1/2 -13 Carbide
Internal and External Thread-Mill
OAL - 3.5"
LOC - 1.0"
Number Flutes 4
Cutter Dia - 0.400"
Order # 60023504
\$213.15**

Page 335 MSC 2006/2007 Catalog





STUDENT STEEL BRIDGE COMPETITION

2015 RULES



Organizing sponsors of the Student Steel Bridge Competition are

- American Institute of Steel Construction (AISC)
- American Society of Civil Engineers (ASCE)

Co-sponsors are

- American Galvanizers Association (AGA)
- American Iron and Steel Institute (AISI)
- Bentley Systems, Inc.
- Canadian Institute of Steel Construction (CISC)
- DS SolidWorks Corp.
- James F. Lincoln Arc Welding Foundation
- National Steel Bridge Alliance (NSBA)
- Nucor Corporation

This document, which is available at <http://www.aisc.org/nssbc>, describes the Student Steel Bridge Competition and states the 2015 rules for both conference and national levels. **Clarifications, which include any revisions to the rules, are published at that web site and do not appear in this document although they are formal addenda to the rules.** The web site includes other information and the form for requesting clarifications. Information at this web site takes priority over any other source except as noted herein.

TABLE OF CONTENTS

	<u>page</u>
1. Mission and Summary	2
2. Introduction	3
3. Problem Statement	4
4. Eligibility	5
5. Safety	7
6. Scoring	7
7. Schedule of Competition	11
8. Material and Component Specifications	12
9. Structural Specifications	14
10. Construction Regulations	17
11. Load Test Instructions	22
12. Equipment Provided by Host	28
13. Interpretation of Rules	29
14. Judging	29
15. Appeals	30
16. Index of Definitions	32
APPENDIX	
Site and Bridge Diagram	33
Loading Diagrams	34

WELCOME

ASCE and AISC support and encourage the equitable opportunity for participation in the Student Steel Bridge Competition by all interested and eligible individuals without regard to race, ethnicity, religion, age, gender, sexual orientation, nationality, or physical challenges. Bridge teams should be inclusive, open, and fair to all interested and eligible participants.

Section 1

MISSION AND SUMMARY

Civil Engineering students are challenged to an intercollegiate competition that supplements their education with a comprehensive, student-driven project experience from conception and design through fabrication, erection, and testing, culminating in a steel structure that meets client specifications and optimizes performance and economy. The Student Steel Bridge Competition increases awareness of real-world engineering issues such as spatial constraints, material properties, strength, serviceability, fabrication and erection processes, safety, aesthetics, project management, and cost. Success in competition requires application of engineering principles and theory, and effective teamwork. Future engineers are stimulated to innovate, practice professionalism, and use structural steel efficiently.

Students design and erect a steel bridge by themselves but may consult with faculty and other advisors. Students gain maximum benefit if they fabricate the entire bridge themselves. However, because appropriate shop facilities and supervision are not available at all universities, students may use the services of a commercial fabricator if they develop the work orders and shop drawings, and observe the operations. Students are encouraged to maximize their involvement in fabrication.

Safety is paramount. AISC and ASCE request that competitors, advisers, hosts, and judges take all necessary precautions to prevent injury to competitors, judges, host personnel, and spectators. Risky procedures are prohibited. Load testing is stopped if sway or deflection exceeds specified limits, or if collapse is imminent. Bridges that cannot be constructed and loaded safely are withdrawn from competition. In addition, the rules identify and penalize construction errors that represent accidents in full-scale construction.

The Student Steel Bridge Competition provides design and management experience, opportunity to learn fabrication processes, and the excitement of networking with and competing against teams from other colleges and universities.

Section 2

INTRODUCTION

The rules simulate a request for proposal that requires a scaled model to demonstrate the efficacy of competing designs. Section 3, “Problem Statement,” relates the rules to realistic challenges encountered in bridge design and construction.

Sections titled “Material and Component Specifications,” “Structural Specifications,” and “Construction Regulations” set standards for strength, durability, constructability, usability, functionality, and safety that reflect the volumes of requirements that govern the design and construction of full-scale bridges. Criteria for excellence in the award categories of stiffness, lightness, construction speed, display, efficiency, and economy are listed in “Scoring.” Competition judges and the Rules Committee take the role of the owner and have authority to accept and reject entries.

The rules accommodate a variety of designs and encourage innovation. Designers must consider the comparative advantages of various alternatives. For example, a through bridge may be stiffer than a deck bridge but slower to construct. Successful teams compare alternatives prior to fabrication using value analysis based on scoring criteria. The rules are changed every year to renew the challenge and ensure that competitors design and build new bridges.

The rules are intended to be prescriptive but may require some interpretation. The procedure for requesting clarification of the rules is described in section 13, “Interpretation of Rules.”

Competitors, judges, and host personnel are encouraged to read this rules document thoroughly from beginning to end and then review the Competition Guide at <http://www.nssbc.info>. That site also is the source of the official scoring spreadsheet which generates forms for recording data. Judges should be familiar with those forms prior to the competition.

Members of the Student Steel Bridge Rules Committee are

- Michael F. Engestrom, Technical Marketing Director, Nucor-Yamato Steel
- Nancy Gavlin, S.E., P.E., Director of Education, AISC
- Jennifer Greer-Steele, Committee on Student Members Corresponding Member, ASCE
- Frank J. Hatfield, P.E., Professor Emeritus, Michigan State University
- Lawrence F. Kruth, P.E., Vice President, Douglas Steel Fabricating Corporation
- John M. Parucki, Structural Steel Consultant
- Leslie Payne, Director, Student and Younger Member Programs, ASCE
- Craig E. Quadrato, P.E., Director, Civil Engineering Design Group, United States Military Academy
- Don Sepulveda, P.E., Executive Officer, Regional Rail, Los Angeles County Metropolitan Transportation Authority

Section 3

PROBLEM STATEMENT

When asked what would most effectively relieve poverty, the President of Kupicra requested a bridge over the Nogo River which bisects his tropical country, inhibiting commerce between farming villages and H'sogo, the capital city.

Transportation and scheduling will be challenges! The proposed site is accessible only by trails which are impassable during the rainy season. Materials must be transported in loads small enough for ox carts. Accelerated Bridge Construction (ABC) is essential to completing the project during a single dry season.

Consultants to the Sonarpin Foundation, which will fund the project, recommend a steel bridge to minimize the weight of material to be transported and erected, and to facilitate prefabrication, which reduces the duration of on-site construction. Durability and ease of maintenance also favor steel.

Piers in the river and surrounding floodplain would be uneconomic due to a deep layer of organic soil. The Nogo is navigable for a few weeks after the rainy season, so the bridge must provide clearance over the river. Low water levels during the dry season preclude the use of barges but allow construction of a temporary causeway crossing from bank to bank.

The scope of the bridge contract does not include footings, deck panels, or causeway, which will be constructed by local crews.

Your company's proposal is among those that the Sonarpin Foundation deems responsive, and winning the contract would establish your team as a leader in implementing Accelerated Bridge Construction technologies in a challenging environment. Each competing firm is requested to submit a 1:10 scale model to demonstrate its concept. Models will be erected under simulated field conditions and will be tested for stability, strength, and serviceability using standardized lateral and vertical loads. Sonarpin consultants and village elders will judge the models by multiple criteria including durability, constructability, usability, stiffness, construction speed, efficiency, economy, and attractiveness. The contract will be awarded to the company whose model satisfies specified requirements and best achieves project objectives.

Any attempt to gain advantage by circumventing the intent of the competition as expressed by the rules, including this problem statement, will be grounds for rejecting the model and terminating the company's eligibility.

Section 4

ELIGIBILITY

4.1 LEVELS OF COMPETITIONS

There are two levels of competition: conference and national. Conference competitions are held in conjunction with ASCE annual student conferences. Outstanding performance in conference competitions qualifies eligible teams for the national competition.

4.2 CONFERENCE COMPETITIONS

4.2.1 Only one bridge per college or university may compete in an ASCE student conference, and a college or university may compete in only one ASCE student conference.

4.2.2 The ASCE student organization that is hosting a conference may invite guest teams, which are teams from colleges or universities that do not have ASCE student organizations, or from official ASCE student organizations that are assigned to different conferences. Conference assignments are listed in the ASCE Official Register at www.asce.org/offreg/.

4.2.3 A team shall consist only of undergraduate and graduate students in good standing with their ASCE student organization during all or part of fall through spring of the current competition academic year. This requirement is waived for guest teams.

4.2.4 The official scoring spreadsheet shall be used, and all teams (including guest teams) shall be listed on that spreadsheet. The official scoring spreadsheet may be downloaded from <http://www.nssbc.info>.

4.2.5 The host student organization shall promptly submit the completed official scoring spreadsheet for a conference competition to ssbc.results@gmail.com. Teams from that conference will not be invited to the National Student Steel Bridge Competition (NSSBC) until the spreadsheet is received and eligibility is confirmed.

4.3. NATIONAL COMPETITION

4.3.1 A team is not eligible to be invited to compete in the NSSBC if it is

- (1) a guest team as defined in sub-section 4.2.2, or
- (2) from an organization that is not in good standing with ASCE, or
- (3) from an organization that has not satisfied ASCE requirements regarding participation in its conference, or
- (4) ruled to be ineligible to complete its conference competition.

ASCE requirements for good standing and for conference participation are listed at www.asce.org/national-eligibility/.

4.3.2 The maximum number of eligible teams from a conference that will be invited to compete in the NSSBC is based on the number of teams at that conference that competed (that is, presented bridges and staged them for timed construction) but not including guest teams as defined in sub-section 4.2.2.

- (1) Only the single best scoring eligible team will be invited from a conference in which two, three, or four non-guest teams competed.
- (2) The two top scoring eligible teams will be invited from a conference in which five to ten non-guest teams competed.
- (3) The three top scoring eligible teams will be invited from a conference in which eleven to nineteen non-guest teams competed.
- (4) The four top scoring eligible teams will be invited from a conference in which twenty or more non-guest teams competed.

4.3.3 Teams are not invited to compete in the NSSBC as guests.

4.3.4 Only one bridge per college or university may be entered in the NSSBC. Bridges may be modified in preparation for NSSBC.

4.3.5 A team shall consist only of ASCE national members of any grade who were students during all or part of the academic year leading up to the NSSBC.

Section 5

SAFETY

Safety has the highest priority – risk of personal injury will not be tolerated. Sub-sections 8.1, 9.2, 9.4, 10.2, 10.3, 11.1, 11.2, 11.5, and 11.6 of these Rules identify hazardous conditions and actions that will result in withdrawing a bridge from competition if not corrected. Judges will document these safety violations by checking appropriate boxes on the data entry forms. Judges also must comply with and enforce the safety regulations for load testing in sub-section 11.2.

Judges are empowered to halt any activity that they deem to be hazardous. If a bridge cannot compete safely, it must be withdrawn from competition. If the problem is not anticipated by the sub-sections listed in the preceding paragraph, the judge should write a brief description of the problem on the data form.

Students are requested to practice safe fabrication procedures and seek appropriate instruction and supervision. The sub-section 8.2 footnote warns of a welding hazard, and precautions listed in sub-section 11.2.3 guide safe load testing prior to competition.

Section 6

SCORING

6.1 RECORDING DATA, ANNOUNCING RESULTS, SUBMITTING SCORES

Scoring data shall be recorded for every team that competes, using judges' scoring forms printed from the official scoring spreadsheet downloaded from <http://www.nssbc.info>. Data from those forms are then entered in the spreadsheet. After all scoring information has been collected for a team, the scoring official reviews data entry with the captain of that team. The captain is given adequate time to verify the data before signing the form. Then a paper or electronic copy of the team's "Computation" worksheet from the scoring spreadsheet is given to the captain, as soon as possible.

The "Rankings" worksheet from the official scoring spreadsheet summarizes the performance of all teams and is distributed at the awards ceremony, electronically or as paper copies.

The completed official scoring spreadsheet for a conference competition shall be submitted to ssbc.results@gmail.com by the host student organization. Conference results are not final until the spreadsheet is submitted. Questions and comments regarding the spreadsheet should be sent to ssbc.results@gmail.com.

Judges' scoring forms shall be retained by the host student organization for two weeks after the competition.

6.2 CATEGORIES OF COMPETITION

Categories of competition are display, construction speed, lightness, stiffness, construction economy, and structural efficiency. In addition, overall performance is rated.

6.2.1 Display

An award is given for Display. The bridge is presented exactly as it will be erected during timed construction. Display is judged by the following criteria

6.2.1.1 Appearance of bridge, including balance, proportion, elegance, and finish. Quality of fabrication, including welding, shall not be considered because some bridges may be fabricated professionally rather than by students.

6.2.1.2 Permanent identification of the bridge consisting of the name of the college or university exactly as shown on the ASCE student web site, www.asce.org/find-a-chapter/. The name shall be formed from steel or applied to steel with paint or decals, and should be easily legible (lettering at least 1" high is recommended). A bridge that lacks appropriate identification will receive a very low display rating.

6.2.1.3 Poster describing design. The poster shall present the following information

- (1) identification of the college or university, using the same name that appears on the bridge,
- (2) brief explanation of why the overall configuration of the bridge was selected,
- (3) scaled, dimensioned side view of the bridge,
- (4) free-body diagram of the bridge for one of the load cases specified in section 7,
- (5) shear and moment diagrams for the bridge considered as a single spanning beam. The diagrams shall correspond to the free-body diagram, and peak magnitudes shall be shown.
- (6) provisions for Accelerated Bridge Construction (ABC), such as design features, construction sequencing, and procedures intended to minimize construction time, and
- (7) acknowledgement of university technicians, faculty, and others who helped fabricate the bridge or provided advice.

The poster shall

- (1) be flat with maximum dimensions of two by three feet,
- (2) present all information on one side,
- (3) not have attached pages that must be lifted or turned, and
- (4) be in English.

Additional information may be included. Names of financial sponsors may be shown on the poster or on an optional second poster that could accommodate their logos. Electronic displays, decorated supports, lights, and sound are not permitted and will result in the worst possible rating for the poster. A very low rating will be imposed if there is no poster or if it is grossly inadequate. The poster is not part of the bridge but must be in place whenever the bridge is on display.

If English is not the dominant language where the competition is conducted, an optional additional poster may be displayed that is a translation into the local language of the required English language design poster.

6.2.1.4 Display is the tie breaker for all categories of competition. Judges shall not declare ties in display.

6.2.2 Construction Speed

The bridge with the lowest total time will win in the construction speed category. Total time is the time required for construction modified by construction penalties prescribed in 9.4, 10.4.2, 10.4.3, and 10.8.1. There is an upper limit on construction time (see 10.8.2).

6.2.3 Lightness

The bridge with the least total weight will win in the lightness category. Total weight is the weight of the bridge (determined by scales provided by the host student organization) plus weight penalties prescribed in 8.2, 9.3, and 9.5. Decking, tools, lateral restraint devices, and posters are not included in total weight.

6.2.4 Stiffness

The bridge with the lowest aggregate deflection will win in the stiffness category. Aggregate deflection is determined from measurements as prescribed in 11.5.

6.2.5 Construction Economy

The bridge with the lowest construction cost (C_c) will win in the construction economy category. Construction cost is computed as

$$C_c = \text{Total time (minutes)} \times \text{number of builders (persons)} \\ \times 50,000 (\$/\text{person-minute}) + \text{load test penalties (\$)}.$$

“Total time” is defined in 6.2.2, “builder” is defined in 10.1.3, and “load test penalties” are prescribed in 11.5. A penalty increment to the number of builders is prescribed in 10.4.1.

6.2.6 Structural Efficiency

The bridge with the lowest structural cost (C_s) will win in the structural efficiency category. Structural cost is computed as

For a bridge that weighs 400 pounds or less,

$$C_s = \begin{aligned} &\text{Total weight (pounds)} \times 20,000 \text{ (\$/pound)} \\ &+ \text{Aggregate deflection (inches)} \times 1,000,000 \text{ (\$/inch)} \\ &+ \text{Load test penalties (\$)} \end{aligned}$$

For a bridge that weighs more than 400 pounds,

$$C_s = \begin{aligned} &[\text{Total weight (pounds)}]^2 \times 50 \text{ (\$/pound}^2\text{)} \\ &+ \text{Aggregate deflection (inches)} \times 1,000,000 \text{ (\$/inch)} \\ &+ \text{Load test penalties (\$)} \end{aligned}$$

“Total weight” is defined in 6.2.3, “aggregate deflection” is defined in 11.5, and “load test penalties” are prescribed in 11.5.

6.2.7 Overall Performance

The overall performance rating of a bridge is the sum of construction cost and structural cost, ($C_c + C_s$). The bridge achieving the lowest value of this total wins the overall competition.

6.3 SPREADSHEET FOR SCORING

The spreadsheet for scoring the competition is also useful for comparing alternatives when designing a bridge. Teams are encouraged to download, understand, and verify the spreadsheet before the competition. It is available in the Competition Guide at <http://www.nssbc.info>. Questions and comments regarding the spreadsheet should be sent to ssbc.results@gmail.com.

Section 7

SCHEDULE OF COMPETITION

In the months before the competition, students design their bridges, fabricate members, test load, practice construction, and select the builders for timed construction.

7.1 RECOMMENDED ORDER OF COMPETITION

The following events occur during the competition

- (1) The official scoring spreadsheet is downloaded from <http://www.nssbc.info/>, and judges' scoring forms are generated from that spreadsheet.
- (2) Bridges are erected for public viewing and are judged for display. After the start of display judging, bridges must not be altered, modified, or enhanced in any way except for repairs prescribed by sub-section 9.4.
- (3) Bridges are disassembled.
- (4) In a meeting at which all team captains are present, the head judge clarifies rules and conditions of the competition, and answers questions.
- (5) The head judge selects the locations of vertical deflection targets and magnitudes of loads. See 11.5 and the Loading Diagrams. Selection is done in the presence of the team captains by rolling a die. For each possible result S of the roll, Table 7.1 gives the dimensions T1 and T2 for positioning the deflection targets, and the magnitudes L1 and L2 of loads.

TABLE 7.1 Determination of T1, T2, L1, and L2

S	T1	T2	L1 (lb)	L2 (lb)
1	9'9"	12'3"	1000	1400
2	7'9"	9'9"	1400	1000
3	7'9"	12'3"	1200	1200
4	7'3"	10'9"	1200	1200
5	7'3"	11'9"	1000	1400
6	9'3"	11'9"	1400	1000

The same locations and loads will be used for all bridges in the same conference competition.

- (6) Using a random process, the head judge determines the order in which teams will compete.
- (7) Bridge members, fasteners, and tools are staged for construction and inspected by the judges. See section 8, "Material and Component Specifications," and sub-sections 10.1.7, 10.2.5, 10.2.6, and 10.6 for details.
- (8) Timed construction. See section 10, "Construction Regulations," for details.
- (9) Judges inspect assembled bridges. For details, see section 9, "Structural Specifications."

- (10) Bridges are weighed (if it is impractical to weigh the entire bridge, its parts may be weighed prior to construction). All bridges shall be weighed, including those that are withdrawn from competition.
- (11) Load testing. See section 11, "Load Test Instructions," for details.
- (12) After a team has completed all phases of the competition, data for the team is transcribed from the judges' scoring forms into the official scoring spreadsheet and checked by the captain. After data entry has been completed, a copy of the team's "Computation" worksheet from the scoring spreadsheet is given to the team captain electronically or on paper.
- (13) Scores and rankings are determined using the official scoring spreadsheet.
- (14) Paper or electronic copies of the "Rankings" worksheet of the official scoring spreadsheet are distributed to captains of all teams at the awards ceremony.
- (15) The host ASCE student organization submits the completed official scoring spreadsheet by e-mailing it to the address given on that spreadsheet.
- (16) The host student organization retains judges' scoring forms for two weeks.

7.2 ALTERNATIVES

The order recommended above may be altered. However, it is essential that

- (1) Bridges are not modified after selection of the load location.
- (2) Bridges are not modified between display judging and timed construction.
- (3) No components or tools are added to or removed from the construction site after staging for inspection.
- (4) Modifications between timed construction and load testing are limited to connection repairs described in sub-section 9.4. Between repairs and load testing, force shall not be applied to the bridge except as necessary to move it. For example, leaning or sitting on the bridge is not allowed.

Section 8

MATERIAL AND COMPONENT SPECIFICATIONS

For the purposes of this competition, steel is defined as an iron alloy that is strongly attracted to the magnet provided by the host organization.

8.1 SAFETY

If any member is not steel, incorporates parts that are not steel, or weighs more than fifteen pounds, the bridge will not be approved for construction or load testing, and will not be eligible for awards in any category. See 8.2.2 for definition of "member."

8.2 DURABILITY AND CONSTRUCTABILITY

Violation of the specifications in this sub-section (8.2) will result in penalties being added to the weight of the bridge. The penalty is 25 pounds for every non-compliant loose bolt and loose nut, and 25 pounds for every non-compliant member plus the weight of that member. See 8.2.2, 8.2.3, and 8.2.4 for definitions of “member,” “loose,” “bolt,” and “nut.”

8.2.1 Bridge

A bridge shall be constructed only of members, loose bolts, and loose nuts. Solder, brazing, and adhesives are not permitted. Exceptions: Purely decorative items such as coatings and decals are permitted, and bridge parts may be labeled.

8.2.2 Members

8.2.2.1 A member is a rigid component comprised of parts welded* together. Bolts and nuts that are welded* to members are parts of members and are not considered to be loose. A member shall retain its shape, dimensions, and rigidity during timed construction and load testing. Members with moving and flexible parts are prohibited. Exception: Deformations caused by mechanical strain (e.g., bending, stretching) during construction and load testing are not violations.

8.2.2.2 A member shall not exceed overall dimensions of 3'0" x 6" x 4". That is, it shall fit into a right rectangular prism (i.e., box) of those dimensions.

8.2.3 Loose Bolts

Loose bolts shall not have parts that flex, move, or are not steel. Nominal length shall not exceed 3" measured from the bottom of the head to the end. Loose bolts shall be commercially available and shall not be mechanically altered or modified in any way but may be painted.

8.2.4 Loose and Welded* Nuts

8.2.4.1 Nuts shall be hexagonal in shape and not have parts that flex, move, or are not steel. Nuts shall be commercially available and shall not be mechanically altered or modified in any way but may be painted.

* **Health advisory:** The bright silvery or colored coating on bolts, nuts, threaded rod, and other hardware contains zinc and cadmium. At welding temperature, both elements create hazardous fumes. Inhalation of zinc fumes causes symptoms resembling those of influenza. Cadmium gas can damage lungs and kidneys, and is a potential carcinogen. **Participants are advised to weld only plain (uncoated) hardware.**

8.2.4.2 Nuts shall have internal threads that extend for the full circumference and length. The threads of a nut shall match the bolt or externally threaded member so that installation and removal require relative rotation.

8.2.5 Holes in Members

8.2.5.1 The hole in a member for a loose bolt or externally threaded part of another member shall be completely surrounded by the member and small enough that the nut or bolt head cannot pass through.

8.2.5.2 Holes in members shall not be threaded. Exception: A nut that is welded to a member and conforms to the specifications of sub-section 8.2.4 is not a violation.

Section 9

STRUCTURAL SPECIFICATIONS

9.1 MEASUREMENT

Conformance with the specifications in this section (9) will be checked with the bridge in its as-built condition after termination of timed construction, before the bridge is moved from the construction site or load tested. The bridge shall not be modified or distorted from its as-built condition in order to conform to these specifications except as prescribed by sub-section 9.4. Dimensions will be checked without decking or applied load.

9.2 FUNCTIONALITY AND SAFETY

If any specification in this sub-section (9.2) is violated, the bridge will not be approved for load testing and will not be eligible for awards in any category.

9.2.1 The bridge shall have two decking support surfaces that are continuous over the full length of the bridge so that decking could be placed anywhere along the span. Decking support surfaces are tops of members. See the Elevation and Section on the Site and Bridge Diagram.

9.2.2 The bridge shall provide access for safely placing 3'6" wide decking and load.

9.2.3 The decking shall not be attached or anchored to the bridge. This prohibition includes but is not limited to protrusions, irregularities, and textures of the decking support surfaces that enhance strength or stability of the bridge.

9.2.4 Decking shall not distort the bridge from its as-built condition.

9.2.5 The bridge shall not be anchored or tied to the floor.

9.2.6 Teams shall construct and load the bridge safely using the site, equipment, and floor surfaces provided by the host student organization. **Bridges and participants shall accommodate local conditions.**

9.3 USABILITY

Specifications in this sub-section (9.3) are illustrated by the Site and Bridge Diagram.

A weight penalty will be assessed for each specification in this sub-section (9.3) that is violated, rather than for every violation of that specification. If there are multiple violations of the same specification, the penalty will be based on the largest violation.

The penalty for violation of each of the specifications in this sub-section (9.3) will be an addition to the weight of the bridge determined as follows

- (1) 50 pounds for a dimensional violation of $\frac{1}{2}$ " or less,
- (2) 100 pounds for a violation greater than $\frac{1}{2}$ " but not exceeding 1",
- (3) 200 pounds for a violation greater than 1" but not exceeding 2", and
- (4) if a violation exceeds 2", the bridge will not be approved for load testing and will not be eligible for awards in any category.

9.3.1 The bridge shall not touch the river or the ground outside the footings. The river is 6'6" wide and the footings are 6'0" from the river banks.

9.3.2 The bridge shall not extend more than 5'0" above the ground or river.

9.3.3 The bridge shall not be wider than 5'0" at any location along the span.

9.3.4 The bridge shall provide a straight rectangular vehicle passageway at least 3'7" wide that completely traverses the bridge from end to end. No part of the bridge, including nuts and bolts, shall be within that minimum width unless it is below the level of the decking support surfaces or at least 1'6" above the level of the decking support surfaces.

9.3.5 Vertical clearance shall be provided under the bridge at all points directly over the river. The clearance shall be at least 1'6" high, measured from the surface of the river. No part of the bridge, including nuts and bolts, shall extend below this limit.

9.3.6 Vertical clearance shall be provided under the bridge at all points directly over the ground. The clearance shall be at least 3 $\frac{1}{2}$ " high, measured from the ground. No part of the bridge, including nuts and bolts, shall extend below this limit. Exception: No clearance is required over the footings.

9.3.7 The decking support surfaces shall be no more than 2'7" above the surface of the river or ground at any point.

9.3.8 Parts of the bridge (including nuts, bolts, and parts that bear on the ground) shall not extend beyond the vertical plane defined by the ends of the decking support surfaces at each end of the bridge.

9.3.9 Decking support surfaces at each end of the bridge shall not extend beyond the vertical plane defined by the footing edge farthest from the river.

9.3.10 The outer edges of the two decking support surfaces shall be no less than 2'6" from one another, and the inner edges of the decking support surfaces shall be no more than 3'2" apart. These dimensions are measured perpendicularly to the span of the bridge. Surfaces outside of the 3'7" limit of specification 9.3.4 are not considered to be decking support surfaces.

9.3.11 Decking support surfaces shall be free of separations and abrupt changes in elevation, except that between segments of decking support surfaces that are surfaces of adjacent members there may be a separation not exceeding $\frac{1}{4}$ ".

9.4 CONNECTION SAFETY

Three minutes will be added to construction time for every connection that violates any specification in this sub-section (9.4) even if it can be corrected.

After termination of timed construction and inspection by the judge, the team is required to attempt to correct every connection that violates specification 9.4.1 or 9.4.2, and will be granted the option to correct connections that violate specifications 9.4.3 or 9.4.4. Only tools that were in the staging yard at the start of timed construction shall be used. A team will be allowed five minutes to correct all connections. If any connection still violates specification 9.4.1 or 9.4.2 when that time limit is reached, the bridge will not be approved for load testing and is not eligible for awards in any category.

9.4.1 Every member shall be connected to every other member that it touches so that they cannot be separated without unscrewing and removing a loose nut or loose bolt, or unscrewing one member from the other.

9.4.2 Every nut shall fully engage the threads of the matching bolt or member. That is, the terminal threads of the bolt or member shall extend beyond or be flush with the outer face of the nut.

9.4.3 Every loose nut shall be tightened sufficiently to contact the member it connects.

9.4.4 Every loose bolt shall be tightened sufficiently so that the head of the bolt contacts the member it connects.

9.5 INSPECTABILITY

All nuts, heads of loose bolts, and threaded ends of bolts and members shall be visible in the completed bridge so that compliance with specifications in sub-section 9.4 can be verified. A penalty of 25 pounds will be added to the weight of the bridge for every threaded end, nut, and bolt head that cannot be inspected.

Section 10

CONSTRUCTION REGULATIONS

10.1 DEFINITIONS

10.1.1 “River,” “staging yard,” “footings,” causeway,” and “construction site boundary” are delineated by the Site Plan on the Site and Bridge Diagram.

10.1.2 “Ground” is the floor inside the construction site boundary, excluding the river but including the causeway and footings.

10.1.3 “Builders” are undergraduate or graduate student members of a team who are within the construction site at the start of timed construction. See section 4, “Eligibility.”

10.1.4 The team designates one builder to serve as “captain” for the entire competition. The captain signifies that the builders are ready to start timed construction, declares the finish, and signs scoring forms.

10.1.5 “Personal protective equipment” consists of a hardhat meeting ANSI standard Z89.1 and protective eyewear or safety goggles meeting ANSI standard Z87.1. A competing organization provides its own personal protective equipment.

10.1.6 A “pouch” is an optional article of clothing that is used to carry nuts, bolts, and tools. This definition encompasses tool belts, magnets, and other accessories worn by builders and having the same function.

10.1.7 A “tool” is a device that is used to construct the bridge but is not part of the completed bridge. A competing organization provides its own tools.

10.1.8 The “constructed portion” is comprised of members, loose nuts, and loose bolts, and is created during timed construction. The constructed portion is not required to be contiguous.

10.1.9 “Member,” “loose bolt,” and “loose nut” are defined in sub-section 8.2.

10.2 GENERAL SAFETY CONDITIONS

Timed construction will not commence or will be stopped if any provision of this sub-section (10.2) is violated.

10.2.1 Builders, judges, host personnel, and spectators shall not be exposed to risk of personal injury.

10.2.2 Only builders and judges are permitted within the construction site boundary during timed construction. Team members who are not builders, coaches, faculty, advisers, other associates of the team, and spectators shall remain in designated areas at a distance from the construction site that assures they are not at risk and cannot interfere with the competition.

10.2.3 There shall be no more than six builders.

10.2.4 At all times during timed construction every builder shall wear personal protective equipment in the proper manner.

10.2.5 A tool shall not weigh more than fifteen pounds. Welding machines and tools requiring external power connections, batteries, or other internal energy supplies shall not be used during timed construction.

10.2.6 Containers of lubricant shall not be in the construction site at any time.

10.3 SAFE CONSTRUCTION PRACTICES

If any rule in this sub-section (10.3) is violated during timed construction, the judge will stop the clock and explain the violation. Before the clock is restarted, builders, tools, members, nuts, and bolts will be returned to the positions they occupied before the violation. Then builders will be asked to resume construction using safe procedures. Builders will have the opportunity to construct their bridge safely. However, if they are not able to construct the bridge completely using safe procedures, construction will cease and the bridge will not be approved for load testing and will not be eligible for awards in any category.

10.3.1 Construction of every non-contiguous part of the constructed portion shall commence by placing a member on the ground within a footing. That member becomes the constructed portion. When a member, loose nut, or loose bolt is in contact with the constructed portion it becomes part of the constructed portion.

10.3.2 At no time shall a builder or builders support the entire weight of the constructed portion or of a non-contiguous part of the constructed portion.

10.3.3 Throwing anything is prohibited.

10.3.4 A builder shall not cross from the ground on one side of the river to the ground on the other side except via the causeway.

10.3.5 Outside the staging yard, a builder shall not simultaneously touch (or touch with tools) more than one member that is not part of the constructed portion.

10.3.6 A pouch or other article of clothing shall not be removed from a builder's person or held in a builder's hand(s).

10.3.7 Nuts, bolts, and tools shall not be held in the mouths of builders.

10.3.8 A builder shall not use the bridge, a constructed portion of the bridge, a member, or a tool to support the builder's body weight. However, a builder may be partially supported by the constructed portion if the builder is kneeling on the floor on both knees, kneeling on the floor on one knee with the other foot on the floor, or standing with the heels and toes of one or both feet on the floor.

10.4 ACCIDENTS

In general, the clock is not stopped when there is an "accident," i.e., an infraction of one of the provisions of this sub-section (10.4).

A penalty is assessed for every accident. If an accident is continuous (for example, a builder stands in the river, or a dropped item is not retrieved promptly) it will be counted as multiple occurrences until corrected. Builders involved in accidents may continue to build. Items involved in accidents shall be recovered promptly and may be used.

Construction cannot depend on deliberately committing an accident. Therefore, the clock will be stopped if any work is accomplished by committing an accident. Before timed construction is resumed, builders, tools, members, nuts, and bolts will be returned to the positions they occupied before the accident.

10.4.1 A builder or builder's clothing touches the river or the floor outside the construction site boundary. For each occurrence, the number of builders is increased by one when the spreadsheet computes construction cost, C_c (the number of builders actually constructing the bridge does not change). Exception: There is no penalty for stepping out of bounds or entering the river to retrieve an object that has been dropped, such as a member, tool, nut, bolt, or personal protective equipment.

10.4.2 A member, constructed portion, tool, loose nut, loose bolt, or personal protective equipment touches the river, the ground outside the staging yard, or the floor outside the construction site. Penalty is 1/4 minute (15 seconds) for every item during every occurrence. Exception: A constructed portion may touch the ground within a footing without penalty.

10.4.3 Outside the staging yard, a member that is not part of the constructed portion touches another member that is not part of the constructed portion. Penalty is 1/4 minute (15 seconds) for every occurrence.

10.5 CONSTRUCTION SITE

See the Site Plan on the Site and Bridge Diagram for layout of the construction site. The host student organization lays out the site before the competition. The construction site shall be laid out so that tape that designates lines is wet or out of bounds. That is, the edges of tapes, not the centerlines, designate the lines shown on the Site Plan.

10.6 START

10.6.1 Before construction begins, only the following are in the staging yard: all builders, members, loose nuts, loose bolts, and tools. Every member, loose nut, loose bolt, and tool must be in contact with the ground and must fit entirely within assigned area of the staging yard as designated on the Site Plan on the Site and Bridge Diagram. Builders are wearing personal protective equipment as well as optional clothing such as pouches. Builders start without tools, nuts, and bolts, which may be passed from one builder to another after timed construction begins.

10.6.2 Judges inspect members, loose nuts, loose bolts, and tools as they are placed in the staging yard. Tools that do not conform to regulation 10.2.5 shall be removed from the staging yard and shall not be used. After inspection and throughout timed construction, additional members, tools, nuts, bolts, or other items shall not be brought into the construction site nor shall anything be removed. Additional builders shall not enter the construction site after the beginning of timed construction.

10.6.3 Timing and construction begin when the captain signifies that the team is ready and the judge declares the start.

10.7 TIME

10.7.1 Time is kept from start to finish of construction. The clock will be stopped under the following conditions

- (1) if a builder or judge sees a condition that could cause injury, or
- (2) when a safety regulation has been violated (see 10.2 and 10.3), or
- (3) when work has been accomplished by committing an "accident." The clock is not stopped if the "accident" does not contribute to the construction process (see 10.4), or
- (4) if a builder or judge is injured.

10.7.2 Construction ceases while the clock is stopped. After the situation has been corrected, builders, tools, and bridge components are returned to the positions they occupied before the interruption, and the clock is restarted.

10.8 TIME LIMIT

10.8.1 If construction time not including penalties exceeds thirty minutes, the scoring spreadsheet will count construction time as 180 minutes. “Accidents” (10.4) that occur after thirty minutes will not be penalized but safety rules (10.2 and 10.3) will still be enforced. Judges may inform the team when this time limit is approaching and shall inform them when it is reached.

10.8.2 If construction time not including penalties exceeds 45 minutes, judges will halt construction. If local conditions allow and the head judge approves, the team may move its bridge off site for continued, untimed construction if it can be done safely. The bridge will not be eligible for awards in any category but, at the discretion of the head judge, it may be load tested after all eligible bridges.

10.9 FINISH

10.9.1 Construction ends and the clock is stopped when

- (1) the bridge has been completed by connecting all the members that were in the staging yard at the start of timed construction,
- (2) all builders are in the staging yard,
- (3) all tools and extra nuts and bolts are held in the hands of builders, or are in clothing worn by builders, or are on the ground in the staging yard, and
- (4) the captain informs the judge that construction is complete.

10.9.2 Installation of decking is not included in timed construction.

10.9.3 After construction is finished the bridge shall not be modified except for repair of connections as prescribed in sub-section 9.4.

Section 11

LOAD TEST INSTRUCTIONS

11.1 DAMAGE

A bridge with damage that would reduce its strength or stability (such as a fractured weld, missing or broken member, broken bolt, or missing nut) will not be approved for load testing and is not eligible for awards in any category. Repair and modifications are not permitted after timed construction except as prescribed by sub-section 9.4.

11.2 SAFETY PRECAUTIONS

It is the responsibility of judges, host personnel, and competitors to employ effectively all precautions, which are summarized in this sub-section (11.2). Competitors should follow the same precautions when proof testing bridges in preparation for competition.

11.2.1 General Precautions

11.2.1.1 An activity shall be halted if the judge considers it to be hazardous. If competitors cannot load their bridge safely, loading will cease and the bridge will not be eligible for awards in any category.

11.2.1.2 Competitors who are not participating in loading, faculty, advisers, and other spectators shall observe from a safe area designated by the judges and host student organization.

11.2.1.3 While participating in load testing, competitors shall wear hardhats meeting ANSI standard Z89.1, protective eyewear or safety goggles meeting ANSI standard Z87.1, work gloves, and leather construction boots. This safety equipment is provided by the competitors. Judges will not permit load testing by competitors who are not wearing the specified safety equipment or are wearing it improperly.

11.2.1.4 Damaged bridges (e.g., broken weld, missing nut, broken bolt, missing or broken member) shall not be tested.

11.2.2 Lateral Load Test Precautions

11.2.2.1 No more than three competitors shall be in the testing area during lateral load tests.

11.2.2.2 Bridges that sway in excess of 1" during lateral load testing shall not be loaded vertically.

11.2.3 Vertical Load Test Precautions

Bridges may collapse suddenly without warning, and a failure may involve only one side so that the load tips sideways. The intent of the provisions of this sub-section (11.2.3) is to prevent personal injury if a bridge collapses.

11.2.3.1 The number of people near the bridge shall be minimized during vertical load tests. No more than three competitors shall be in the testing area during a vertical load test.

11.2.3.2 Safety supports shall be provided by the host organization, and shall be of adequate strength, height, and number to arrest falling load if a bridge collapses.

11.2.3.3 Safety supports shall be in place under the decking units before load is placed on the bridge.

11.2.3.4 The number and location of safety supports under a decking unit shall be sufficient to arrest the load even if only one side or one end of the bridge collapses. Therefore, safety supports are needed under the sides and ends of the decking units, not just in the middle. Safety supports should be directly under decking units rather than under bridge trusses or cross braces, if possible.

11.2.3.5 Safety supports shall be adjusted individually for each bridge so that load cannot drop more than 5". If the height of the safety supports is not adjustable in appropriate increments, they shall be augmented with pieces of wood or other suitable material provided by the host student organization.

11.2.3.6 No one shall reach, crawl, or step under a bridge while any portion of vertical load is in place. If safety supports must be adjusted during loading, the load shall first be removed without disturbing the bridge, adjustments made, and the load replaced as it was before being removed.

11.2.3.7 Bridges that inhibit safely placing vertical load shall not be tested.

11.2.3.8 Load on the decking shall not exceed 400 psf or 500 pounds concentrated.

11.2.3.9 Judges shall observe sway carefully during vertical load testing. If sway exceeds 1", loading shall cease and load shall be removed carefully.

11.2.3.10 Judges shall observe vertical deflections carefully. If deflection at any target exceeds 3", loading shall cease and load shall be removed carefully.

11.2.3.11 Judges shall observe the behavior of the bridge. Loading shall cease and the load shall be removed carefully if, in the opinion of a judge, collapse is imminent.

11.3 PREPARATION

The captain shall observe the load tests.

The judge designates the “A” side of the bridge by a random process. The “B” side is opposite the “A” side. “Left” and “right” ends are determined by facing the “A” side from the outside of the bridge.

Teams shall accept imperfect field conditions such as bent decking, sloping floors, and unfavorable floor surfaces.

At their discretion, judges may impose a penalty for a bridge that incorporates parts having the primary function of interfering with placement of targets, decking, load, or measuring devices. If the bridge cannot be loaded safely, or sway or deflection cannot be measured in accordance with the provisions of this section (11), the bridge shall not be load tested and is not eligible for awards in any category.

“Sway” is translation in any horizontal direction. Typically, sway is determined by using a plumb bob attached to the bridge at a specified target. A sway requirement is failed if any part of the bridge causes the displacement of the plumb bob at floor level to exceed the specified limit, even if the plumb bob is not attached to that part.

11.4 LATERAL LOAD TEST

The provisions of this sub-section (11.4) are illustrated by the Lateral Load Test detail on the Loading Diagrams drawing.

The lateral load test is conducted with one decking unit placed at the center of the bridge and approximately 75 pounds of weight on the decking near the “B” side of the bridge. This load is intended to restrain the bearing surfaces of the bridge from lifting off the floor when lateral load is applied. No additional uplift restraint will be used, even if bearing surfaces lift.

Bearing surfaces are prevented from sliding by lateral restraint applied by competitors. This lateral restraint does not restrain rotation or uplift. The restraint is applied as close to the floor as possible, at the locations shown on the Lateral Load Test detail. Competitors may provide and use optional devices to prevent sliding. The lateral load test is failed if the bridge is restrained in other than the lateral direction, or if the restraint is not applied close to the ground, or if the restraint is not effective.

A sway target is established for measurement on the “A” side of the bridge, 9'9” from the right end of the decking support surface. The sway target is located at the level of the decking or at the top of the decking support surface, which is the bottom of the decking.

Apply a fifty-pound lateral pull and measure the sway. The pulling force is located as close as possible to the decking support surface and not more than 4” from the sway target. To pass the lateral load test, the sway must not exceed 1”.

If the bridge does not pass the lateral load test it is not approved for further testing and is not eligible for awards in any category. Do not conduct any other load test. Check the appropriate box on the judges’ scoring form.

If the bridge passes the lateral load test, proceed with the vertical load test.

11.5 VERTICAL LOAD TEST

The provisions of this section are illustrated by the Vertical Load Test details on the Loading Diagrams drawing. “Deflection” is translation in a vertical direction.

Safety supports are placed under the decking so that no portion of the load will drop more than approximately 5” if the bridge collapses.

Decking units are 3’0” long in the longitudinal (span) direction of the bridge. Two decking units are used for the vertical load test. Place the decking units so that they abut one another with the abutting edges 9’9” from the right end of the decking support surfaces.

Decking units are placed square with the bridge and centered on the decking support surfaces. If grating is used for decking, it is placed with the main bars spanning laterally. Decking units shall not be attached to the bridge and shall not distort it (see 9.2.4).

Three vertical deflection targets are located as close as possible to the decking support surface, which is at the same level as the bottom of the decking. The targets are at the following locations

- A side at a distance T1 from the right end of the decking support surface.
- A side at a distance T2 from the right end of the decking support surface.
- B side 9’9” from the right end of the decking support surface.

T1 and T2 are determined at the beginning of the competition as described by Table 7.1 in section 7, “Schedule of Competition.”

Position measuring devices on the three vertical deflection targets.

Uniformly distribute fifty pounds of preload on each of the two decking units. The preloads are laterally centered on the decking unit. The preloads are located and aligned identically for every bridge.

A decking unit that does not contact the decking support surface at a vertical deflection target will be clamped to the decking support surface at or near that location until the preload has been placed and the vertical deflection measuring devices have been initialized. The clamp will be removed before additional load is placed.

If deflection data is lost (for example, by malfunction or displacement of a measuring device), the judge will require the team to disassemble the bridge and repeat timed construction beginning with the initial conditions prescribed in 10.6. Scoring will be based on the run that results in the larger construction cost, C_c (not including load test penalties), but will not exceed 125% of C_c (not including load test penalties) for the initial run.

Vertical loading produces three measurements

- (1) D1A = absolute value of vertical deflection at the target on the “A” side at T1.
- (2) D2A = absolute value of vertical deflection at the target on the “A” side at T2.
- (3) DB = absolute value of vertical deflection at the target on the “B” side.

The scoring spreadsheet computes aggregate deflection as the sum of those three measurements, rounded to the nearest 0.01”.

Load the bridge and measure the deflections, using the following procedure

- (1) The preload remains in place.
- (2) Initialize the sway measurement device.
- (3) Initialize the three vertical deflection measuring devices or record the initial readings.
- (4) Competitors place L1 pounds of additional load on the right decking unit, and then place L2 pounds of load on the left decking unit. L1 and L2 are determined at the beginning of the competition as described by Table 7.1 in section 7, “Schedule of Competition.” Load is laterally centered on the decking unit and is distributed over the length of the decking unit as uniformly as possible at all times during loading. Load is distributed and aligned identically for every bridge. Load shall be placed at a steady pace, without hesitation.
- (5) As the load is being placed, observe the deflection and sway targets. Stop loading if
 - (a) sway exceeds 1”, or
 - (b) deflection at any deflection target exceeds 3” downward, or
 - (c) decking or any part of the bridge, other than the intended bearing surfaces, comes to bear on a safety support or the floor, or
 - (d) a decking unit or some of the load falls off the bridge, or
 - (e) the bridge collapses or a dangerous collapse is imminent, in the opinion of the judge.

If loading is stopped for any of the situations a, b, c, d, or e, the bridge is not approved for further load testing and is not eligible for awards in any category. Remove the load and **do not continue load testing**. Check the appropriate box on the judge’s scoring form.

If the bridge passes, record the final readings for D1A, D2A, and DB. If any of those values exceeds 2”, the scoring spreadsheet will add penalties of \$8,000,000 to the Construction Economy score and \$20,000,000 to the Structural Efficiency score.

11.6 Unloading

If the bridge collapses during unloading (situation c, d, or e), it is not eligible for awards in any category.

Section 12

EQUIPMENT PROVIDED BY HOST

12.1 SOURCES OF INFORMATION

Equipment for hosting a competition is listed and described by the Competition Guide at <http://www.nssbc.info>. This site also includes competition procedures and illustrations of bridge details that demonstrate compliance and non-compliance with specifications and regulations. Host personnel, judges, and competitors are encouraged to review the site.

Although the equipment described in this section (12) will be provided by the host organization, competitors should acquire similar equipment for load testing before the competition.

12.2 DECKING

Preferred decking is steel bar grating identified as W-19-4 (1" x $\frac{1}{8}$ "). The dimensions of a unit of grating are approximately 3'6" x 3'0" x 1" and the weight is approximately 50 pounds. However, the host may provide a different type of decking with approximately the same dimensions. Grating has significant bending strength only in the direction of the main bars, which are 3'6" long. The grating will be installed with the main bars perpendicular to the length of the bridge, creating a roadway that is 3'6" wide. Therefore, support for the grating is needed for the edges that are parallel to the length of the bridge but not for the edges that are perpendicular to the length.

12.3 SAFETY SUPPORTS

Safety supports must be used during load tests and are intended to limit the consequences of a bridge collapsing. Safety supports shall be of sufficient height, strength, number, and extent so that none of the load will fall more than approximately 5" if the bridge collapses. Safety supports may be steel, nested stacks of plastic buckets, timbers, sand bags, or masonry units.

12.4 LOAD

A total load of 2500 pounds should be supplied in uniform pieces of size and weight that can be handled safely. When in place, the load should not provide significant stiffness in the longitudinal direction of the bridge. The recommended load consists of 25-pound lengths of 5" x 5" x $\frac{5}{16}$ " steel angle placed perpendicular to the length of the bridge. Sacks of material, containers of liquid, concrete blocks, or jacking systems could be used. Decking is not included as part of the 2500 pound load.

Section 13

INTERPRETATION OF RULES

The web site <http://www.aisc.org/nssbc> lists clarifications of the rules. Competitors, judges, and host personnel may submit questions via a form on that web site but should **first read the previously posted clarifications, reread this rules document carefully in its entirety, and review the Competition Guide at <http://www.nssbc.info>.** Submitters' names and affiliations must accompany clarification requests and will be posted with the questions and answers. Internet deliberation by the SSBC Rules Committee typically requires one to two weeks but possibly longer. Questions must be submitted before 5:00 PM Eastern Daylight Saving Time, May 4, 2015.

Section 14

JUDGING

The host student organization will recruit judges. Judges are empowered to halt any activity that they deem to be hazardous. Judges have full authority over conduct of the competition and interpretation of the rules. Decisions, scoring, and ranking are the sole responsibility of the judges and will be final. The host student organization will assure that the judges are fully informed of the rules and procedures, and fully equipped for their tasks. More information for host organizations and judges is available at <http://www.aisc.org/nssbc> and at <http://www.nssbc.info>, where the official scoring spreadsheet may be downloaded and the Competition Guide reviewed.

Section 15

APPEALS

15.1 CONFERENCE COMPETITIONS

15.1.1 At the beginning of the competition each team will identify its captain. The host organization will identify the conference head judge (CHJ).

15.1.2 A penalty, decision, measurement, score, or condition of competition may be appealed only by the team captain and only to the CHJ. The CHJ will not hear the appeal if he or she is approached by students other than the team captain. The CHJ will refuse to hear protests regarding bridges other than the captain's. The appeal must be made as soon as possible after the situation becomes apparent. The CHJ will hear the appeal as soon as possible and may interrupt the competition. If the captain does not consent to the decision of the CHJ, he or she shall write an explanation on the judge's scoring sheet before signing it. Participants are reminded that civility and ethical behavior are expected during the competition and particularly concerning appeals.

15.1.3 After the conference competition, the team captain has the option to appeal the decision of the CHJ by e-mail to Ms. Maria Mnookin <mnookin@aisc.org> or by letter to Ms. Mnookin (AISC, Suite 700, One E. Wacker Dr., Chicago, IL 60601-2001). The e-mail message or letter shall include

- (1) name of the college or university making the appeal,
- (2) captain's name, e-mail address, postal address, and telephone number,
- (3) faculty adviser's name, e-mail address, postal address, and telephone number,
- (4) brief description of the problem, including citation of pertinent rules,
- (5) action taken at the competition to deal with the problem,
- (6) action that the appealing team feels should have been taken,
- (7) data showing that the team should have qualified for national competition, and
- (8) captain's signature (letter only).

The SSBC Rules Committee may ask the host student organization to provide judges' scoring forms documenting the problem and may confer with the CHJ.

15.1.4 Appeals must be made by e-mail or letter. An appeal will be considered only if the e-mail is received or the letter is postmarked by 5:00 PM Eastern Daylight Saving Time on the Wednesday immediately after the conference competition. Ms. Mnookin will forward the appeal to the SSBC Rules Committee for their evaluation. The Committee will not respond to an appeal until the official scoring spreadsheet for that conference has been submitted by the host organization to ssbc.results@gmail.com.

The only redress that may be made is an invitation to participate in the national competition if the Committee is convinced that the appeal is valid and that the appealing team should have qualified for the national competition. Decisions and rankings made by conference judges will not be overturned.

15.2 NATIONAL COMPETITION

15.2.1 Judges will refuse to hear protests from a team concerning any bridge other than their own.

15.2.2 A penalty, decision, measurement, score, or condition of competition may be appealed only by a team captain and only to the station head judge (SHJ). The SHJ will not hear the appeal if he or she is approached by students other than the team captain. The appeal must be made as soon as possible after the situation becomes apparent and before the conditions at issue are changed (e.g., by further construction, loading, or disassembly of the bridge). The SHJ will hear the appeal as soon as possible and will make a ruling. The conditions at issue will not be changed during deliberation. Participants are reminded that civility and ethical behavior are expected during the competition and particularly concerning appeals.

15.2.3 After hearing the SHJ's ruling, the team captain may request a five-minute recess to discuss the issue with the team. During the recess, the conditions at issue will not be changed. Immediately after that recess, if the team has justification to contest the SHJ's ruling, the captain has the option to appeal that decision to the national head judge (NHJ). The NHJ will hear the appeal as soon as possible and will make a ruling. The NHJ may consult with the SSBC Rules Committee. The conditions at issue will not be changed during deliberation.


15.2.4 If the team has justification to contest the NHJ's ruling, the team captain has the option to appeal that decision directly to the SSBC Rules Committee within fifteen minutes after hearing the NHJ's ruling. The Committee may request information from the NHJ and SHJ but those judges will not vote on the final ruling.

15.2.5 The decision of the SSBC Rules Committee is final; there are no further appeals. However, AISC and ASCE welcome written suggestions for improving future competitions.

Section 16

INDEX OF DEFINITIONS


Accelerated bridge construction	Load 11.5, 12.4
3, 6.2.1.3	Loose bolt 8.2.2.1, 8.2.3
Accident 10.4	Loose nut 8.2.2.1, 8.2.4
Aggregate deflection 11.5	T1, T2 7, 11.5
Bolt 8.2.3	Member 8.2.2
Bridge 8.2.1	Nut 8.2.4
Builder 10.1.3	Overall performance 6.2.7
Captain 10.1.4	Personal protective equipment
Causeway 10.1.1	10.1.5
Constructed portion 10.1.8	Pouch 10.1.6
Construction cost 6.2.5	Preload 11.5
Construction economy 6.2.5	River 10.1.1
Construction site boundary 10.1.1	S 7
Construction speed 6.2.2	Safety 5
D1A, D2A, DB 11.5	Safety supports 11.2.3, 12.3
Decking 11.5, 12.2	Scoring form 6.1
Decking support surface 9.2.1	Scoring spreadsheet 6.1
Deflection 11.5	Staging yard 10.1.1
Display 6.2.1	Steel 8
Footing 10.1.1	Stiffness 6.2.4
Ground 10.1.2	Structural cost 6.2.6
Guest team 4.2.2	Structural efficiency 6.2.6
Judge 14	Sway 11.3
L1, L2 7, 11.5	Target 11.4, 11.5
Lateral restraint device 11.4	Team 4.2.3, 4.3.5
Lightness 6.2.3	Tool 10.1.7




NOTES:

1. LENGTH CAN BE ADJUSTED TO FIT SITE CONDITIONS.
2. BRIDGE SHALL ACCOMMODATE DECKING THROUGHOUT OVERALL LENGTH OF THE BRIDGE.
3. NO PART OF THE BRIDGE SHALL EXTEND BEYOND DECKING SUPPORT SURFACES (AT BOTH ENDS).
4. DECKING SUPPORT SURFACES SHALL NOT EXTEND BEYOND THE EDGE OF THE FOOTING (AT BOTH ENDS).
5. 'GROUND' IS THE AREA WITHIN THE CONSTRUCTION SITE BOUNDARY INCLUDING THE FOOTINGS AND CAUSEWAY BUT EXCLUDING THE RIVER.

SITE PLAN - REFER TO CHAPTERS 9 & 10



ELEVATION - REFER TO CHAPTER 9



SECTION A

REV	BY	DATE	APP	REC NO	EXPIRES	SEAL HOLDER	DESCRIPTION

DESIGNED BY: F. HATFIELD
 DRAWN BY: D. SEFULVEDA
 CHECKED BY: RULES COMM.
 IN CHARGE: N. GAYLIN
 DATE: 08-20-2014



ASCE-AISC
 STUDENT STEEL BRIDGE CONTEST

SITE AND BRIDGE
 DIAGRAM

CONTRACT NUMBER:
 DRAWING NO.: DWG 1
 SCALE: NTS
 SHEET NO.:



1. SAFETY SUPPORTS TO BE IN PLACE UNDER THE LOAD AND TO REMAIN AT ALL TIMES DURING LOADING.
2. ALL LOADING SAFETY PROCEDURES TO BE FOLLOWED.
3. LATERAL RESTRAINT MUST BE APPLIED CLOSE TO THE GROUND AND MUST NOT RESTRAIN ROTATION, UPLIFT, OR TRANSLATION IN OTHER THAN THE LATERAL DIRECTION.
4. LOCATION OF 50 lb. PULL SHALL NOT EXCEED 4' FROM SWAY TARGET.
5. SWAY TARGET IS TO REMAIN IN PLACE THROUGHOUT LOADING PROCESS.
6. LOADS ARE CENTERED Laterally AND DISTRIBUTED OVER THE DECKING UNIT AS UNIFORMLY AS POSSIBLE DURING LOADING.
7. OBSERVE SWAY AND TERMINATE LOADING IF SWAY EXCEEDS 1 INCH.

[illegible]